







DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION				
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN		REMOVE	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	SHSM	PROJECT SHEET #	STANDARD SHEET #
																	(LB / FT)				(LB / FT)								
BAKERSFIELD VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS							
SB	4.328	F	W3-5	36	36		TRIM 	5/5	9.00						2	30.00	X						INSTALL 32 FT SOUTH OF UTILITY POLE #32 AT M.P. 4.334	X					
SB	4.233	F	R2-1	30	36			5/5	7.50						1	14.00	X						INSTALL 100 FT NORTH OF EXISTING, ACROSS FROM NB 40 MPH	X					
SB	4.224	F	R2-1	24	30		SPEED LIMIT 35	5/5					1		X														
		F	R3-1	24	24		NO RIGHT TURN SYMBOL	5/5					1																
		F	VD-700	6	10		MILE MARKER	5/5			1	1	1									SALVAGE AND MOUNT ON NEW POST BELOW NO RIGHT TURN SYMBOL							
		F	R3-1	24	24		TRIM 	5/5	4.00						1	13.00	X						REQUIRES VEGETATION CLEARING	X					
SB	4.098	G	VR-017	24	30		LLL 24,000 LBS	5/5					1		X														
		G	VD-700	6	10		MILE MARKER	5/5			1	1	1									SALVAGE AND MOUNT ON NEW POST BELOW FOUR WHEELER SIGN							
		G	VR-017	24	30			5/5	5.00						1	15.50	X						EGYPT RD (TH-20)		9				
		G	UNK.	24	30		FOUR WHEELERS PROHIBITED ON TOWN HIGHWAYS	5/5				1										EGYPT RD (TH-20); MOUNT SALVAGED SIGN BELOW LLL							
SB	4.090	E/F	D3-1	UNK.	UNK.		EGYPT RD	5/5					1		X														
		G	UNK.	24	30		FOUR WHEELERS PROHIBITED ON TOWN HIGHWAYS	5/5			1	1										SALVAGE AND MOUNT IN NEW LOCATION							
		H	R1-1	30	30		STOP	5/5					1																
		G	VD-700	6	10		MILE MARKER 	5/5			1	1	1									SALVAGE AND MOUNT ON NEW POST BELOW STOP SIGN							
		E/F	D3-1	38	12			5/5	3.17						1	13.75	X						EGYPT RD (TH-20); MOUNT TO STOP SIGN WITH BRACKET		13				
SIGN SUMMARY SHEET							SHEET TOTALS	28.67	0.00	0	4	4	9	0	0	6	86.25		0	0.0	0.0	0.0	0.0	PROJECT NAME: STOWE - BERKSHIRE					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT		EA	LB	LB	LB	LB	PROJECT NUMBER: STPG SIGN (49)					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	235.0	0.0	6	11	11	58	0	0	43	645.0		0		0.0			FILE NAME: 06 BAKERSFIELD VT-108 SB T	PLOT DATE: 6/25/2015				
																							PROJECT MANAGER: D. BRYANT	DRAWN BY: J. BLANCHARD					
																							DESIGNED BY: J. BLANCHARD	CHECKED: K. KERN					
																							BAKERSFIELD SB SHEET 4	SHEET 96	OF	131			