DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
BAKERSFIELD VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		H	R1-1	30	30		5/5	6.25																			EGYPT RD (TH-20)	X		
SB	3.898	F	S1-1	36	36	FYG	SCHOOL SYMBOL 5/5						1		X														
		F	W16-9P	30	18	FYG	AHEAD WARNING 5/5						1																
		F	VD-700	6	10		MILE MARKER 5/5				1	1	1														SALVAGE AND MOUNT ON NEW POST BELOW SCHOOL SIGN			
		F	S1-1	36	36	FYG	5/5	9.00								1			13.50 X										
		F	S4-3P	24	8	FYG	5/5	1.33																				X		
SB	3.894	E/F	D3-1	UNK.	UNK.		AVENUE RD 5/5						1		X														
		G	VR-017	24	30		LLL 24,000 LBS 5/5						1																
		G	UNK.	UNK.	UNK.		SCHOOL ZONE 25 MPH 5/5				1		1														SALVAGE TO NEW LOCATION			
		H	R1-1	30	30		STOP 5/5						1																
SB	3.894	G	VR-017	24	30		TRIM 5/5	5.00								1			14.00 X								AVENUE RD (TH-31); INSTALL 30 FT BEYOND STOP SIGN ASSEMBLY		9	
		G	UNK.	UNK.	UNK.		SCHOOL ZONE 25 MPH 5/5					1															AVENUE RD (TH-31); SALVAGE AND REMOUNT BELOW LLL			
SB	3.884	E/F	D3-1	40	12		5/5	3.33																			AVENUE RD (TH-31); MOUNT TO STOP SIGN WITH BRACKET		13	
		H	R1-1	30	30		5/5	6.25								1		13.75 X								AVENUE RD (TH-31); INSTALL IN PAVEMENT WITH DRUM AROUND POST(SEE GENERAL NOTE 7, SHT 2)	X		
SB	3.831	F	M2-1	21	15	GRN/WHT	5/5	2.19								1		14.25 X								INSTALL 111 FT NORTH OF EXISTING	X		
							SHEET TOTALS	33.35	0.00	0	2	2	7	0	0	4		~~60.0~~ 55.50		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	235.0	0.0	6	11	11	58	0	0	43		645.0		0			0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**

FILE NAME: **06 BAKERSFIELD VT-108 SB T** PLOT DATE: **7/29/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
BAKERSFIELD SB SHEET 5 SHEET **96** OF **131**