DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ENOSBURG VT-108 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	2.164	A	W7-1	30	30		HILL SYMBOL 5/2						1		X														
		A	W7-2b	24	18		TRUCKS USE LOWER GEAR 5/2						1																
		A	W7-1	30	30		5/2	6.25								1		15.50 X									X		
		A	W7-2bP	24	18		5/2	3.00																			X		
NB	2.207	A	R2-1	24	30		SPEED LIMIT 40 4/29						1		X														
		A	R2-1	30	36		4/29	7.50								1		13.75 X									X		
NB	2.265	A	W2-1	30	30		CROSSROADS SYMBOL 5/2						1		X														
		A	W13-1P	24	24		30 MPH 5/2						1																
		A	W2-1	30	30		5/2	6.25								1		13.50 X									X		
		A	W13-1P	18	18		5/2	2.25																			X		
NB	2.370	A	W11-6H	30	30		SNOWMOBILE SYMBOL 5/2						1		X														
		A	W11-6H	30	30		TRIM 5/2	6.25								1		12.50 X										INSTALL IN CLOSED POSITION		9	
NB	2.376	C	VR-017	24	30		TRIM 4/28	5.00								1		14.00 X										TYLER BRANCH RD (TH-1); INSTALL 20 FT EAST OF END OF FENCE; REQUIRES VEGETATION CLEARING		9	
NB	2.387	C/D	D3-1	UNK.	UNK.		W ENOSBURG RD VT 108S 5/2						1		X														
		A/B	D3-1	UNK.	UNK.		TYLER BRANCH RD 5/2						1																
SIGN SUMMARY SHEET							SHEET TOTALS	36.50	0.00	0	0	0	8	0	0	5		69.25 ~~75.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	198.6	0.0	2	5	5	42	0	0	38		570.0		0	0.0								

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **07 ENOSBURG VT-108 NB TSS** PLOT DATE: **4/15/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
ENOSBURG NB SHEET 2 SHEET **101** OF **131**