DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND		NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
ENOSBURG VT-108 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		D	R1-1	30	30		STOP	4/28						1															
		C	VR-017	24	30		LLL 24,000 LBS	4/28						1															
		D	R1-1	30	30			4/28	6.25								1		13.50 X								TYLER BRANCH RD (TH-1)	X		
NB	2.387	A/B	D3-1	66	12			5/2	5.50								2		22.25 X								TYLER BRANCH RD (TH-1)		14	
NB	2.406	A	R2-1	24	30		SPEED LIMIT 40	4/29						1		X													
		A	VD-700	6	10		MILE MARKER	4/29				1	1	1													SALVAGE AND MOUNT ON NEW POST BELOW SPEED LIMIT SIGN			
		A	R2-1	24	30			4/29	5.00								1		13.75 X									X		
NB	2.444	A	M3-1	24	12		NORTH STATE	4/29						1		X													
		A	M1-5A	30	24		VERMONT 108	4/29						1															
		A	M3-1	24	12	GRN/WHT	TRIM	4/29	2.00								1		15.50 X									X		
		A	M1-5	30	24	GRN/WHT		4/29	5.00																				E-136B
NB	2.558	A	R2-1	24	30		SPEED LIMIT 50	4/29						1		X													
		A	R2-1	24	30			4/29	5.00								1		12.75 X									X		
NB	2.659	A	W1-10	30	30		MODIFIED LEFT CURVE	4/29						1		X													
		A	W13-1P	18	18		35 MPH	4/29						1															
SIGN SUMMARY SHEET							SHEET TOTALS		28.75	0.00	0	1	1	9	0	0	6		77.75 ~~90.0~~		0	0.0	0.0	0.0	0.0					
									SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS		198.6	0.0	2	5	5	42	0	0	38		570.0		0	0.0								

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **07 ENOSBURG VT-108 NB TSS** PLOT DATE: **4/15/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
ENOSBURG NB SHEET 3 SHEET **102** OF **131**