DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
BERKSHIRE VT-108 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.000	C	VD-024	60	7.5		BERKSHIRE/ENOSBURG TRIM 6/28			1				X															
		A	VR-039	24	18		STATE HIGHWAY BEGINS 4/26				1		1														SALVAGE AND MOUNT TO NEW POST IN SAME LOCATION			
		A	R2-1	24	30		SPEED LIMIT 50 4/26				1		1														SALVAGE AND MOUNT TO NEW POST IN SAME LOCATION			
		C	VD-700	6	10		MILE MARKER 4/26			1																			
		C	VD-700	6	10		MILE MARKER 4/26			1																			
NB	0.000	A	VR-039	24	18		STATE HIGHWAY BEGINS 4/26					1				1		14.50 X									SALVAGE FROM EXISTING LOCATION			
		A	R2-1	24	30		SPEED LIMIT 50 4/26					1															SALVAGE FROM EXISTING LOCATION			
NB	0.201	A	M3-1	24	12		NORTH STATE 4/26						1		X														
		A	M1-5	30	24		VERMONT 108 4/26						1																
		A	M3-1	24	12	GRN/ WHT	TRIM 4/26	2.00								1		14.25 X										X		
		A	M1-5	30	24	GRN/ WHT	4/26	5.00																					E-136B
NB	0.465	A	W1-10	30	30		MODIFIED RIGHT CURVE 4/26						1		X														
		A	W13-1P	18	18		35 MPH 4/26						1																
NB	0.520	A	W1-2R	30	30		TRIM 6/28 4/26	6.25								1		16.00 X									INSTALL 290 FT NORTH OF EXISTING; REQUIRES VEGETATION CLEARING	X		
		A	W13-1P	18	18		4/26	2.25																				X		
SIGN SUMMARY SHEET							SHEET TOTALS	15.50	0.00	3	2	2	6	0	0	3		44.75 ~~45.0~~		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	332.5	0.0	5	6	5	68	0	0	57		855.0		0	0.0								

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **09 BERKSHIRE VT-108 NB TSS** PLOT DATE: **6/24/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
BERKSHIRE NB SHEET 1 SHEET **111** OF **131**