DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
BERKSHIRE VT-108 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.543	A	W11-4	30	30		CATTLE SYMBOL 4/26						1		X														
NB	0.558	A	W11-4	30	30		TRIM 6/28 4/26	6.25								1		14.75 X								INSTALL 79 FT NORTH OF EXISTING; REQUIRES VEGETATION CLEARING	X		
NB	1.123	A	W1-2R	30	30		RIGHT CURVE 4/26						1		X														
		A	W13-1P	18	18		35 MPH 4/26						1																
NB	1.183	A	W1-2R	30	30		TRIM 4/26	6.25								1		14.75 X								INSTALL 317 FT NORTH OF EXISTING; INSTALL 10 FT SOUTH OF MAILBOX NEAR THIS LOCATION	X		
		A	W13-1P	18	18		4/26	2.25																			X		
NB	1.927	A	S3-1	30	30		SCHOOL BUS STOP AHEAD TRIM 6/28 4/26						1		X															
		A	S3-1	36	36	FYG	4/26	9.00								2		27.25 X								REQUIRES VEGETATION CLEARING	X		
NB	2.022	A	VW-054L	30	30		HIDDEN DRIVE LEFT 4/27						1		X														
		A	VW-133L	30	30		TRIM 4/27	6.25								1		15.25 X										10	
NB	2.301	A	W11-4	30	30		CATTLE SYMBOL 4/27						1		X														
		A	W11-4	30	30		4/27	6.25								1		16.00 X									X		
NB	2.462	A	W1-2L	30	30		LEFT CURVE 4/27						1		X														
		A	W1-2L	30	30		TRIM 4/27	6.25								1		17.00 X									X		
NB	3.220	C	VR-017	24	30		4/27	5.00								1		14.75 X								COLLINS RD (TH-25)		9	
SIGN SUMMARY SHEET							SHEET TOTALS	47.50	0.00	0	0	0	7	0	0	8		~~119.75~~ 120.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	332.5	0.0	5	6	5	68	0	0	57		855.0		0	0.0								

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **09 BERKSHIRE VT-108 NB TSS** PLOT DATE: **6/24/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
BERKSHIRE NB SHEET 2 SHEET **112** OF **131**