DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
BERKSHIRE VT-108 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	3.220	C	W14-2	30	30		NO OUTLET			1				X															
NB	3.229	C	D3-1	UNK.	UNK.		WEST BERKSHIRE RD						~~1~~ 0		X														
		B	D3-1	UNK.	UNK.		COLLINS RD						~~1~~ 0																
		C	UNK.	UNK.	UNK.		CIDERBUCK FARM				1		~~1~~ 0														SALVAGE AND RETURN TO TOWN			
		D	R1-1	30	30		STOP 4/27						1																
		C	VD-700	6	10		MILE MARKER 4/27				1	1	1														SALVAGE AND MOUNT ON NEW POST BELOW STOP SIGN			
		D	R1-1	30	30		TRIM 4/27	6.25								1	~~14.75~~ X									COLLINS RD (TH-25)	X		
NB	3.229	A/B	D3-1	56	12		5/3	4.67								2	~~26.25~~ X									COLLINS RD (TH-25); FIELD LOCATE FOR VISIBILITY FROM VT 108		14	
NB	4.251	A	W3-5	36	36		5/3	9.00								2	~~31.50~~ X									INSTALL 74 FT NORTH OF MAIL BOX #5281 AT M.P. 4.237	X		
NB	4.272	A	W3-5	36	36		SPEED REDUCTION SPEED LIMIT 40 5/3						1		X														
NB	4.344	A	R2-1	24	30		SPEED LIMIT 40 TRIM 6/28 4/27						1		X														
		A	R2-1	30	36		TRIM 4/27	7.50								1	~~13.25~~ X										X		
NB	4.439	A	VD-018	30	18		WEST BERKSHIRE CANADA BORDER 2 5/3						1		X														
NB	4.446	A	W3-5	36	36		TRIM 5/3	9.00								2	~~33.00~~ X									INSTALL 37 FT NORTH OF EXISTING VILLAGE SIGN	X		
NB	4.493	A	VD-018	30	18		5/3	3.75								1	~~15.00~~ X									INSTALL 250 FT NORTH OF NEW SPEED REDUCTION SIGN AT M.P. 4.446; REQUIRES VEGETAION CLEARING		6	
SIGN SUMMARY SHEET							SHEET TOTALS	40.17	0.00	1	2	1	~~5~~ 8	0	0	9	~~133.75~~ 135.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	332.5	0.0	5	6	5	68	0	0	57	855.0			0	0.0								

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**

FILE NAME: **09 BERKSHIRE VT-108 NB TSS** PLOT DATE: **6/24/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
BERKSHIRE NB SHEET 3 SHEET **113** OF **131**