DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
BERKSHIRE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	5.556	H	R1-1	30	30		STOP			1				X															
		G	VD-700	6	10		MILE MARKER			1																			
		E/F	D3-1	48	12		5/4	4.00																		LAKE RD (VT-120); MOUNT TO STOP SIGN WITH BRACKET		14	
SB	5.500	F	M3-3	24	12		SOUTH STATE 4/25						1		X														
		F	M1-5	30	24		VERMONT 108 4/25						1																
		F	M3-3	24	12	GRN/WHT	TRIM 4/25	2.00					2			1		15,25 X								X		
		F	M1-5	30	24	GRN/WHT		5.00																					E-136B
SB	5.461	F	D2-1	72	12		ENOSBURG FALLS 6 5/4						1		X														
		F	VD2-1	72	12		TRIM 5/4	6.00								2		27,50 X								REQUIRES VEGETATION CLEARING		8	
SB	5.372	F	R2-1	24	30		SPEED LIMIT 50 4/25						1		X														
		F	R2-1	24	30		4/25	5.00					1			1		15,50 X								X		
SB	5.202	F	W3-5	36	36		SPEED REDUCTION SPEED LIMIT 40 5/4						1		X														
		F	VD-700	6	10		MILE MARKER 5/4				1	1	1														SALVAGE AND MOUNT ON NEW POST BELOW SPEED REDUCTION WARNING			
		F	W3-5	36	36		TRIM 5/4	9.00								2		25,50 X								X		
SB	5.099	F	R2-1	24	30		SPEED LIMIT 40 TRIM 6/28 4/25						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	31.00	0.00	2	1	1	~~10~~ 7	0	0	6		~~83.75~~ 90.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	328.8	0.0	6	4	4	66	0	0	56		840.0		0	0.0								

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **10 BERKSHIRE VT-108 SB TSS** PLOT DATE: **6/25/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
BERKSHIRE SB SHEET 4 SHEET **124** OF **131**