DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
BERKSHIRE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
		F	VD1-1a	72	12		5/4	6.00																				8	
SB	4.832	F	M3-3	24	12		SOUTH STATE 8/16						1		X														
		F	M1-5	30	24		VERMONT 118 8/16						1																
		F	M6-3	21	15		^UP ARROW STATE 8/16						1																
		F	M3-3	24	12		SOUTH STATE 8/16						1																
		F	M1-5	30	24		VERMONT 108 8/16						1																
		F	M6-1	21	15		RIGHT ---> STATE 8/16						1																
		F	M3-3	24	12	BLK/WHT	8/16	2.00								2			33.00 X	2					2C	SLIP BASE REQUIRED - SEE SHEET 2 8/16/16	X		
		F	M5-1	30	24	BLK/WHT	8/16	5.00																				E-136C
		F	M6-3	21	15	BLK/WHT	8/16	2.19																			X		
		F	M3-3	24	12	GRN/WHT	8/16	2.00																			X		
		F	M1-5	30	24	GRN/WHT	8/16	5.00																				E-136B
		F	M6-1R	21	15	GRN/WHT	8/16	2.19																			X		
SB	4.821	C/D	D3-1	68	12		w Berkshire Rd VT108 5/4	5.67								2			23.00 X							INSTALL IN LINE WITH CATCH BASIN, 58 FT SOUTH OF ROUTE ASSEMBLY		14	
		A/B	D3-1	68	12		w Berkshire Rd VT108 5/4	5.67																				14	
SIGN SUMMARY SHEET							SHEET TOTALS	35.71	0.00	0	0	0	6	0	0	4			~~60.0~~ 56.00	~~0~~ 2	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA			FT	EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	328.8	0.0	6	4	4	66	0	0	56			840.0	0		0.0							

PROJECT NAME: **STOWE - BERKSHIRE**
PROJECT NUMBER: **STPG SIGN (49)**
FILE NAME: **10 BERKSHIRE VT-108 SB TSS** PLOT DATE: **7/29/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
BERKSHIRE SB SHEET 6 SHEET **126** OF **131**