DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
BERKSHIRE VT-108 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	0.101	F	W3-5	36	36		5/4	9.00								2		30.50 X							INSTALL 121 FT SOUTH OF EXISTING	X		
SB	0.064	F	VD-018	30	18		ENOSBURG FALLS JCT VT 105 5/4						1		X													
		F	VD-018	30	18		Enosburg Falls Jct VT 105 5/4	3.75								1		13.00 X									6	
SB	0.000	F	VR-038	24	18		STATE HIGHWAY ENDS TRIM 5/4			1				X														
		F	R2-1	24	30		SPEED LIMIT 35 5/4			1															REQUIRES VEGETATION CLEARING			
							SHEET TOTALS	12.75	0.00	2	0	0	1	0	0	3		43.50 ~~45.0~~		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	328.8	0.0	6	4	4	66	0	0	56		840.0		0		0.0						

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STOWE - BERKSHIRE
PROJECT NUMBER: STPG SIGN (49)

FILE NAME: 10 BERKSHIRE VT-108 SB TSS
PROJECT MANAGER: D. BRYANT
DESIGNED BY: J. BLANCHARD
BERKSHIRE SB SHEET 10

PLOT DATE: 6/25/2015
DRAWN BY: J. BLANCHARD
CHECKED BY: K. KERN
SHEET 130 OF 131