DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
CALAIS VT-14 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.000	A	R2-1	24	30		SPEED LIMIT 50			1				X															
NB	0.039	A	S3-1	36	36	FYG	SCHOOL BUS STOP AHEAD			1				X															
NB	0.326	A	VD-062B	72	16		BUSINESS SIGN			1				X															
NB	0.690	A	VW2-1M	36	36		MODIFIED CROSSROAD						1		X														
		A	W16-8a	UNK.	UNK.		<--- LIGHTENING RIDGE RD/MAX GRAY RD						1																
7/19/16		A	W2-1	30	30			6.25								1			16'-0" X							X		
		A	W16-8aP	48	15			5.00																		5	
NB	0.771	A	D1-1	72	20		<--- CALAIS ELEM SCHOOL						1		X														
		A	VD1-2	72	20			10.00								2		14'-9" X 12'-9"								5	
NB	0.799	A	VR-173	36	48		LEFT TURN ONLY AT BREAK IN CENTER LINE						1		X														
		A	VR-173	36	48			12.00								2		13'-6" X 13'-6"								6	
7/15/16																													
NB	0.825	A/B	D3-1	UNK.	UNK.		MAX GRAY RD						1		X														
		A/B	D3-1	42	12			~~4.33~~ 3.50								1		X 10'-9"								8	
NB	0.826	C	VR-017	24	30		LLL 24,000 LBS						1		X														
		C	UNK.	UNK.	UNK.		NEIGHBORHOOD WATCH				1		1														SALVAGE AND RETURN TO TOWN			
							SHEET TOTALS	37.58	0.00	3	1	0	7	0	0	6		90.0		0	0.0	0.0	0.0	0.0			
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB			
							TOWN DIRECTIONAL TOTALS	210.8	0.0	8	13	9	52	0	0	42		630.0		0			0.0				

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: CALAIS - GREENSBORO
PROJECT NUMBER: STPG SIGN(50)

FILE NAME: 01 CALAIS VT-14 NB.xls
PROJECT MANAGER: D. BRYANT
DESIGNED BY: J. BLANCHARD
CALAIS NB SHEET 1

PLOT DATE: 5/19/2015
DRAWN BY: J. BLANCHARD
CHECKED K. KERN
SHEET 10 OF 66