	DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
	WOODBURY VT-14 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
8/11/16	SB	5.475	F	W2-1	30	30		CROSSROAD						1		X														
	SB	5.442	F	W2-1	30	30			6.25								1		14'-3" X								INSTALL 174 FT SOUTH OF EXISTING CROSSROAD SIGN	X		
	SB	5.404	F	VD-062AL	72	16		BUSINESS SIGN			1				X														
8/11/16	SB	5.376	F	S3-1	36	36	FYG		9.00								2		14'-6" X 15'-0"								INSTALL 148 FT SOUTH OF BUSINESS SIGN	X		
	SB	5.324	G	VR-017	24	30		LLL 24,000 LBS						1		X														
			G	VR-017	24	30			5.00								1		13'-0" X								GREENWOOD LAKE RD (TH-7)		6	
	SB	5.320	H	R1-1	30	30		STOP						1		X														
			G	VD-700	6	10		MILE MARKER				1	1	1													GREENWOOD LAKE RD (TH-7); SALVAGE AND MOUNT ON NEW POST BELOW STOP SIGN			
			H	R1-1	30	30			6.25								1		14'-6" X								GREENWOOD LAKE RD (TH-7)	X		
	SB	5.320	E/F	D3-1	UNK.	UNK.		GREENWOOD LAKE RD			1				X												GREENWOOD LAKE RD (TH-7); REQUIRES VEGETAION CLEARING			
8/10/16	SB	5.051	E/F	D3-1	UNK.	UNK.		PVT ICE HOUSE RD						1		X														
			E/F	D3-1	58	12			~~4.83~~ 5.33								2		12'-0" X 11'-3"								ICE HOUSE RD (PVT)		8	
8/12/16	SB	4.858	E/F	D3-1	UNK.	UNK.		MEADOW LN PVT						1		X														
			E/F	D3-1	50	12			~~4.17~~ 4.67								2		11'-0" X 10'-9"								MEADOW LN (PVT)		8	
	SIGN SUMMARY SHEET							SHEET TOTALS	36.50 SF	0.00 SF	2 EA	1 EA	1 EA	6 EA	0 EA	0 EA	9 EA		135.0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
	VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	291.8	0.0	13	13	13	69	0	0	62		930.0		0	0.0								

PROJECT NAME: **CALAIS - GREENSBORO**
PROJECT NUMBER: **STPG SIGN (50)**

FILE NAME: **04 WOODBURY VT-14 SB TSS.** PLOT DATE: **5/19/2015**
PROJECT MANAGER: **D. BRYANT** DRAWN BY: **J. BLANCHARD**
DESIGNED BY: **J. BLANCHARD** CHECKED **K. KERN**
WOODBURY SB SHEET 2 SHEET **35** OF **66**