DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
WOODBURY VT-14 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	3.446	F	R2-1	24	30		SPEED LIMIT 50						1		X														
		F	R2-1	24	30			5.00								1		13'-3" X								X		
SB	3.240	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
		F	VD-700	6	8		MILE MARKER						1																
SB	3.165	F	S3-1	36	36	FYG		9.00								2		16'-6" X 14'-9"								INSTALL 396 FT SOUTH OF EXISTING SBSA	X		
SB	1.892	E/F	D3-1	UNK.	UNK.		MAPLE RD						1		X														
		E/F	D3-1	34	12			~~2.83~~ 3.17								1		13'-3" X								MAPLE RD (TH-49); MOUNT TO STOP SIGN POST WITH BRACKET		8	
		H	R1-1	30	30			6.25																		MAPLE RD (TH-49)	X		
		G	VD-700	6	10		MILE MARKER					1														SALVAGE FROM EXISTING POST; MOUNT BELOW STOP SIGN			
SB	1.892	H	R1-1	30	30		STOP						1		X														
		G	VD-700	6	10		MILE MARKER				1		1														SALVAGE TO NEW POST			
SB	1.892	G	VR-017	24	30		LLL 24,000 LBS						1		X														
		G	VR-017	24	30			5.00								1		13'-9" X								MAPLE RD (TH-49)		6	
SB	1.784	F	W2-2	30	30		RIGHT SIDE ROAD						1		X														
		F	VD-700	6	8		MILE MARKER MILE MARKER WASN'T THERE						~~1~~																		
							SHEET TOTALS	28.42	0.00	0	1	1	9	0	0	5		75.0		0	0.0	0.0	0.0	0.0						
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB						
							TOWN DIRECTIONAL TOTALS	291.8	0.0	13	13	13	69	0	0	62		930.0		0	0.0									

7/27/16

7/26/16

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: CALAIS - GREENSBORO
PROJECT NUMBER: STPG SIGN (50)

FILE NAME: 04 WOODBURY VT-14 SB TSS. PLOT DATE: 5/19/2015
PROJECT MANAGER: D. BRYANT DRAWN BY: J. BLANCHARD
DESIGNED BY: J. BLANCHARD CHECKED K. KERN
WOODBURY SB SHEET 6 SHEET 39 OF 66