DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB/FT) 1.88	SQUARE STEEL (IN) 2.00 (LB/FT) 2.42	SQUARE STEEL (IN) 2.50 (LB/FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB/FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB/FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB/FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB/FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
HARDWICK VT-14 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	0.000	C	VD-024	60	7.5		HARDWICK/WOODBURY			1				X															
		C	VD-025	60	7.5		CALEDONIA CO/WASHINGTON CO			1				X															
		C	VD-700	6	8		MILE MARKER			1																			
		C	VD-700	6	8		MILE MARKER			1																			
NB	0.241	A	W3-5	36	36		SPEED REDUCTION SPEED LIMIT 40						1		X														
NB	0.263	A	W3-5	36	36			9.00								2		14'-6" X 13'-3"								INSTALL 116 FT NORTH OF EXISTING SPEED REDUCTION WARNING	X		
NB	0.358	A	R2-1	24	30		SPEED LIMIT 40						1		X														
		A	R2-1	30	36			7.50								1		13'-3" X									X		
NB	0.628	A	R2-1	24	30		SPEED LIMIT 40						1		X														
		A	R2-1	24	30			5.00								1		13'-6" X									X		
NB	0.679	C	R2-1	24	30		SPPED LIMIT 35 LEFT "AS IS"				~~1~~	~~1~~	~~1~~		X	1											CAREY RD (TH-48); SALVAGE AND MOUNT ON NEW POST BELOW LLL			
		C	VR-017	24	30			5.00																		CAREY RD (TH-48); INSTALL 180 FT FROM VT-14 BETWEEN SNACK BAR PARKING LOT AND DRIVEWAY		6	
NB	0.688	D	R1-1	30	30		STOP						1		X														
		C	VD-700	6	10		MILE MARKER				1	1	1														CAREY RD (TH-48); SALVAGE AND MOUNT TO NEW POST BELOW STOP SIGN			
		A/B	D3-1	34	12			~~2.83~~ 3.17								1		13'-9" X										CAREY RD (TH-48); MOUNT TO STOP SIGN POST WITH BRACKET		9	
							SHEET TOTALS	29.67	0.00	4	2	2	6	0	0	6		90.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
							TOWN DIRECTIONAL TOTALS	174.0	0.0	16	10	7	51	0	0	37		555.0		0	0.0							

8/12/16

8/15/16

8/12/16

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **CALAIS - GREENSBORO**
PROJECT NUMBER: **STPG SING (50)**
FILE NAME: **05 HARDWICK VT-14 NB TSS.dgn**
PROJECT MANAGER: **D. BRYANT**
DESIGNED BY: **J. BLANCHARD**
HARDWICK NB SHEET 1
PLOT DATE: **5/19/2015**
DRAWN BY: **J. BLANCHARD**
CHECKED **K. KERN**
SHEET **43** OF **66**