DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
HARDWICK VT-14 NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	1.517	A	R2-1	24	30		SPEED LIMIT 40			1				X														
NB	1.567	A	M3-1	24	12		NORTH STATE						1		X													
		A	M1-5	24	24		VERMONT 14						1															
		A	M3-1	24	12	GRN/ WHT		2.00								1		14'-0" X								X		
		A	M1-5	24	24	GRN/ WHT		4.00																				E-136B
NB	1.790	A	R2-1	24	30		SPEED LIMIT 50						1		X													
		A	R2-1	24	30			5.00								1		11'-9" X								X		
NB	2.615	A	R2-1	24	30		SPEED LIMIT 50						1		X													
		A	VD-700	6	8		MILE MARKER						1															
NB	3.615	A/B	D3-1	12	56		SMITH FARM RD					1				2		11'-6" X 11'-3"								SMITH FARM RD (TH-8); SALVAGE FROM EXISTING LOCATION		
NB	3.617	C	VR-017	24	30		LLL 24,000 LBS			1				X												SMITH FARM RD (TH-8)		
		C	VD-700	6	8		MILE MARKER			1																		
NB	3.624	A/B	D3-1	12	56		SMITH FARM RD				1		1	X												SALVAGE AND MOUNT TO NEW LOCATION		
		D	R1-1	30	30		STOP			1																SMITH FARM RD (TH-8)		
							SHEET TOTALS	11.00	0.00	4	1	1	6	0	0	4		60.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	174.0	0.0	16	10	7	51	0	0	37		555.0		0	0.0								

8/18/16

8/19/16

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: CALAIS - GREENSBORO
PROJECT NUMBER: STPG SING (50)
FILE NAME: 05 HARDWICK VT-14 NB TSS.) PLOT DATE: 5/19/2015
PROJECT MANAGER: D. BRYANT DRAWN BY: J. BLANCHARD
DESIGNED BY: J. BLANCHARD CHECKED K. KERN
HARDWICK NB SHEET 7 SHEET 49 OF 66