

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	TRAINING	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							140				140		CY	COMMON EXCAVATION	203.15	2			
							10				10		CY	SOLID ROCK EXCAVATION	203.16	-			
							3015				3015		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27	29			
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
							1165				1165		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	8			
							145				145		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	2			
							5				5		CWT	EMULSIFIED ASPHALT	404.65	-			
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
							20				20		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST			
							20				20		HR	TRUCK RENTAL	608.37	EST			
							20				20		HR	LOADER RENTAL, TYPE I	608.40	EST			
							47				47		MGAL	DUST CONTROL WITH WATER	609.10	-			
							368				368		CY	STONE FILL, TYPE II	613.11	3			
							1310				1310		CY	STONE FILL, TYPE IV	613.13	12			
							107				107		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-			
							7				7		EACH	ENERGY ABSORPTION ATTENUATOR	621.56	-			
							1				1		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
							372				372		LF	REMOVE AND RESET GUARDRAIL	621.75	-			
							26				26		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	1			
							610				610		LF	TEMPORARY TRAFFIC BARRIER	621.90	EST			
							80				80		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
							500				500		HR	FLAGGERS	630.15	EST			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	EST			
								500			500		HR	EMPLOYEE TRAINEESHIP	634.10	-			
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
							1				1		LS	TRAFFIC CONTROL	641.10	-			
							2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
							1470				1470		LF	4 INCH WHITE LINE	646.20	10			
							1470				1470		LF	4 INCH YELLOW LINE	646.21	10			
							1700				1700		SY	GEOTEXTILE UNDER STONE FILL	649.31	7			
									47		47		SY	GEOTEXTILE FOR SILT FENCE	649.51	1			
									16		16		LB	SEED	651.15	1			
									1		1		LB	SEED, WINTER RYE	651.17	EST			
									130		130		LB	FERTILIZER	651.18	4			
									0.6		0.6		TON	AGRICULTURAL LIMESTONE	651.20	-			
									0.6		0.6		TON	HAY MULCH	651.25	-			
							35				35		CY	TOPSOIL	651.35	1			
							1044				1044		SY	GRUBBING MATERIAL	651.40	10			

PROJECT NAME: WOODSTOCK
 PROJECT NUMBER: STP 024(40)
 FILE NAME: z13c014qs.dgn
 PROJECT LEADER: D. BRYANT
 DESIGNED BY: T. KELLEY
 QUANTITY SHEET 1
 PLOT DATE: 2/4/2015
 DRAWN BY: T. KELLEY
 CHECKED BY: D. BRYANT
 SHEET 8 OF 27

