

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						2				2		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-			
						306				306		LF	BOX BEAM GUARDRAIL	621.30	-			
						4				4		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-			
						4				4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 3 RAIL BOX BEAM	621.725	-			
						400				400		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	2.74			
						100				100		HR	UNIFORMED TRAFFIC OFFICERS	630.10	-			
						500				500		HR	FLAGGERS	630.15	-			
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
									3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
						520				520		HR	EMPLOYEE TRAINEESHIP	634.10	-			
						1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
						5				5		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
						1390				1390		LF	4 INCH WHITE LINE	646.20	7.31			
						1350				1350		LF	4 INCH YELLOW LINE	646.21	4.4			
						30				30		LF	24 INCH STOP BAR	646.26	2.44			
						4				4		EACH	LETTER OR SYMBOL	646.30	-			
								700		700		SY	GEOTEXTILE UNDER STONE FILL	649.31	8.36			
							210			210		SY	GEOTEXTILE FOR SILT FENCE	649.51	2.84			
							120			120		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	6.1			
							130			130		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61	2.59			
							20			20		LB	SEED	651.15	6.62			
							20			20		LB	SEED, WINTER RYE	651.17	6.62			
							120			120		LB	FERTILIZER	651.18	8.5			
							0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20	0.05			
							0.5			0.5		TON	HAY MULCH	651.25	0.05			
							140			140		CY	TOPSOIL	651.35	5.81			
								380		380		SY	GRUBBING MATERIAL	651.40	13.89			
							1			1		LS	EPSC PLAN	652.10	-			
							40			40		HR	MONITORING EPSC PLAN	652.20	-			
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
							450			450		SY	TEMPORARY EROSION MATTING	653.20	2.89			
							30			30		CY	VEHICLE TRACKING PAD	653.35	-			
							50			50		LF	BARRIER FENCE	653.50	7.3			
							1150			1150		LF	PROJECT DEMARCATION FENCE	653.55	0.31			
							1.08			1.08		SF	TRAFFIC SIGNS, TYPE A	675.20	-			
							70			70		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-			
							12			12		EACH	REMOVING SIGNS	675.50	-			
							3			3		EACH	ERECTING SALVAGED SIGNS	675.60	-			

PROJECT NAME: BRADFORD	PLOT DATE: 15-SEP-2016
PROJECT NUMBER: BF 0191 (29)	DRAWN BY: G. ROY
FILE NAME: s13c054qs.dgn	CHECKED BY: M. EVANS-MONGEON
PROJECT LEADER: C. CARLSON	SHEET 8 OF 71
DESIGNED BY: G. ROY	
QUANTITY SHEET (2)	