STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
VT 25B 12+59.6 RT	Appleton Rd	1					X				2					11'-3" ~~X~~ 11'-6"			X																	
VT 25B 13+16.5 RT	STOP	1					X				1					13'-0" ~~X~~			X																	
	0252 0901 0017	1	6	10	0.42																												VD-700 0252 / 0901 / 0017			T-44
VT 25B 13+94.1 RT	BRIDGE 1 VT 25B	1	6	8	0.33						1				6'-6" ~~X~~				X														VD-701 LINE 2: 1 LINE 3: VT 25B			T-42
VT 25B 15+34.5 LT	BRIDGE 1 VT 25B	1	6	8	0.33						1				6'-6" ~~X~~				X														VD-701 LINE 2: 1 LINE 3: VT 25B			T-42
TH 51 20+48.6 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1					X				1					13'-5" ~~X~~			X																	

POST TOTALS									FT	FT	FT	FT 14	FT 56	FT		EA	LB	LB	LB		LB	LB	LB	LB											
SUB-TOTAL	SF 1.08	SF	EA	SF					FT			FT ~~70~~					LB			EA	LB				EA	EA	LB								
TOTALS	SF 1.08	SF	EA	SF					FT			FT ~~70~~ 62.17'					LB			EA	LB				EA	EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE."
SHS = STANDARD HIGHWAY SIGNS

PROJECT NAME: BRADFORD
PROJECT NUMBER: BF 0191 (29)

FILE NAME: sl3c054trfbdr.dgn
PROJECT LEADER: C. CARLSON
DESIGNED BY: G. ROY
TRAFFIC SIGN SUMMARY

PLOT DATE: 15-SEP-2016
DRAWN BY: G. ROY
CHECKED BY: M. EVANS-MONGEON
SHEET 21 OF 71