

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	US5 - BRIDGE NO. 144	US5 - BRIDGE NO. 147	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
								515	340		855		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								30	10		40		GAL	WATER REPELLENT, SILANE	514.10				
								204	62		266		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
								720	185		905		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
								102	62		164		LF	JOINT SEALER, HOT POURED	524.11				
								720	185		905		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
								72	18		90		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
								36	9		45		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
								11	1		12		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
								6500	1650		8150		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
								180			180		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
								200	50		250		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
								130	50		180		GAL	REPOINTING GRANITE BRIDGE CURB	616.225				
								80	50		130		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
								150	100		250		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
								1			1		LS	TRAFFIC CONTROL (US ROUTE 5 - BRIDGE NO. 144)	641.10				
									1		1		LS	TRAFFIC CONTROL (US ROUTE 5 - BRIDGE NO. 147)	641.10				
								4	2		6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
								600	310		910		LF	4 INCH WHITE LINE	646.20				
								600	310		910		LF	4 INCH YELLOW LINE	646.21				
								2500	2040		4540		LF	TEMPORARY 4 INCH WHITE LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6011				
								3000			3000		LF	TEMPORARY 4 IN YELLOW LINE, TEMPORARY PAVEMENT MARKING TAPE	646.6111				
								50	51		101		EACH	LINE STRIPING TARGETS	646.76				
								2000	2040		4040		SF	PAVEMENT MARKING MASK	646.86				
									1		1		EACH	SPECIAL PROVISION (TEMPORARY TRAFFIC SIGNAL SYSTEM, PORTABLE)	900.620				
								22			22		LF	SPECIAL PROVISION (SIDEWALK EXPANSION JOINT)	900.640				
								1	1		2		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
								1	1		2		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
								200	75		275		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				
								11	6		17		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H or CRS-1H)	900.683				

PROJECT NAME: LYNDON  
PROJECT NUMBER: BF MEMB(39)

FILE NAME: z\3C\22frm.dgn  
PROJECT LEADER: G. BOGUE  
DESIGNED BY: D. DEBAIE  
QUANTITY SHEET QS-1

PLOT DATE: 5/22/2014  
DRAWN BY: P. ARMATA  
CHECKED BY: J. HUNGERFORD  
SHEET 4 OF 28

