

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	LANDSCAPING	EROSION CONTROL	BRIDGE #10	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1					1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			
						75					75		CY	COMMON EXCAVATION	203.15	9.8			
						5					5		CY	SOLID ROCK EXCAVATION	203.16	2.5			
									220		220		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27	5.1			
						70					70		CY	GRANULAR BORROW	203.32	9.3			
						1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST			
									210		210		CY	STRUCTURE EXCAVATION	204.25	4			
									190		190		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	3.3			
									3		3		GAL	WATER REPELLENT, SILANE	514.10	0.4			
									1		1		LS	PRECAST CONCRETE STRUCTURE (NORTH WALL)	540.10	-			
									1		1		LS	PRECAST CONCRETE STRUCTURE (SOUTH WALL)	540.10	-			
						70					70		CY	CONTROLLED DENSITY (FLOWABLE) FILL	541.45	4.8			
						20					20		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST			
						40					40		HR	TRUCK RENTAL	608.37	EST			
						20					20		HR	LOADER RENTAL, TYPE I	608.40	EST			
								390			390		CY	STONE FILL, TYPE II	613.11	5			
									220		220		CY	STONE FILL, TYPE IV	613.13	4			
						800					800		HR	FLAGGERS	630.15	EST			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
						1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
						1					1		LS	TRAFFIC CONTROL	641.10	-			
						2					2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
									25		25		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	3.7			
								65			65		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	1			
								30			30		LB	SEED	651.15	4			
								210			210		LB	FERTILIZER	651.18	2.3			
								0.9			0.9		TON	AGRICULTURAL LIMESTONE	651.20	0.1			
								0.2			0.2		TON	HAY MULCH	651.25	0.03			
								250			250		SY	GRUBBING MATERIAL (6")	651.40	9			
								1			1		LS	EPSC PLAN	652.10	-			
								10			10		HR	MONITORING EPSC PLAN	652.20	EST			
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
								1650			1650		SY	TEMPORARY EROSION MATTING	653.20	39			
								36			36		CY	VEHICLE TRACKING PAD	653.35	0.2			
								625			625		LF	BARRIER FENCE	653.50	2			
								490			490		LF	PROJECT DEMARCATION FENCE	653.55	8			
								16			16		EACH	EVERGREEN TREES (PICEA GLAUCA)(5')(B&B)	656.20	-			
								17			17		MGAL	LANDSCAPE WATERING	656.65	0.4			

PROJECT NAME: HIGHGATE
PROJECT NUMBER: STP SCRPI(2)
FILE NAME: d13ci34_frm.dgn PLOT DATE: 14-OCT-2016
PROJECT LEADER: B. MARTIN DRAWN BY: A. KEMPTON
DESIGNED BY: A. KEMPTON CHECKED BY: M. GAMELIN
QUANTITY SHEET 1 SHEET 13 OF 40