STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
VT. ROUTE 73 ROCHESTER: R 452+33.0, RT		1	30	30	6.25						1					X		X													WI-2R		
R 454+08.0, RT	0730 1415 0860	1	6	10	0.42						1				X			X													SIGN ID CODE VD-700			T-44
R 455+31.0, RT		1	30	30	6.25						1					X		X													W3-1		
R 456+92.0, RT	← Rochester 1 ← Waterbury 38	1 1	72 72	12 12	6.00 6.00						2						X	X												SIGN ID CODE VDI-1A SIGN ID CODE VDI-1A		123 123	
	Stockbridge 7 → Killington 18 →	1 1	72 72	12 12	6.00 6.00																									SIGN ID CODE VDI-1A SIGN ID CODE VDI-1A POSTS SHALL BE INSTALLED ON SLIP BASES PAID FOR UNDER ITEM 900.620 SPECIAL PROVISION (SOIL BEARING SLIP BASE)(2 1/2")		123 123	
R 459+74.0, RT	END JCT	1 1	24 21	12 15	2.00 2.19						2					X		X											IB	SIGN ID CODE M4-6 GREEN ON WHITE SIGN ID CODE M2-1 GREEN ON WHITE			E-136B E-136B
	VERMONT 73 VERMONT 100	1 1	24 30	24 24	4.00 5.00																									SIGN ID CODE VMI-5 GREEN ON WHITE SIGN ID CODE VMI-5 GREEN ON WHITE			E-136B E-136B
	THIS SHEET SUBTOTAL SHEET 112 SUBTOTAL SHEET 113 SUBTOTAL				50.11 30.44 3.78										8 40 72	56 56 -	28 - -																
	SHEET 114 SUBTOTAL SHEET 115 SUBTOTAL SHEET 116 SUBTOTAL				~~14.11~~ 19.11 2.94 24.20		- + -								56 56 48	42 14 56																
	SHEET 117 SUBTOTAL SHEET 118 SUBTOTAL SHEET 119 SUBTOTAL				30.43 22.77 45.33		+3 - 1								24 40 -	84 56 154																
	SHEET 120 SUBTOTAL SHEET 121 SUBTOTAL				30.68 ~~37.09~~ 37.25										32 16	70 84	- 14															
	ROUNDING				0.12										18	8	8															
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VAOT "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF 410	LF 680	LF 50		EA		LB	LB	LB	LB								
	TOTALS				SF ~~292~~ 297.04	SF	EA. ~~3~~ 4	SF				LF			LF 1140					EA.	LB				EA.	EA.	LB					

CHA

PROJECT NAME: ROCHESTER
PROJECT NUMBER: ER STP 0162(21)

FILE NAME: z13c176tsss.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: J. OLSEN
TRAFFIC SIGN SUMMARY SHEET #11

PLOT DATE: 1/11/2017
DRAWN BY: J. HEALD
CHECKED BY: J. SHIELDS
SHEET 122 OF 360