

**CULVERT INVENTORY TABLE**

**CULVERT INVENTORY TABLE**

CULVERT NO.	INVERT IN				INVERT OUT				PIPE	COMMENT
	STATION	POSITION	OFFSET FROM HCL	ELEVATION	STATION	POSITION	OFFSET FROM HCL	ELEVATION		
<b>RANDOLPH (VT ROUTE 12A)</b>										
1	26+12.0	RIGHT	18.12	673.86	26+11.0	LEFT	23.75	671.65	18" CPEP	RETAIN 45'
2	28+16.4	RIGHT	15.95	672.50	28+21.4	LEFT	23.94	670.58	18" CMP	NEW 18" X 40" CPEP(SL), CONSTRUCT HEADWALL AT INLET
3	32+04.9	RIGHT	17.65	665.36	32+04.7	LEFT	26.46	662.11	15" CMP	RETAIN
4	33+84.1	RIGHT	14.30	667.89	33+82.8	LEFT	23.22	664.62	15" CMP	RETAIN
5	39+56.8	RIGHT	23.53	682.55	39+53.6	LEFT	17.28	679.50	24" CMP	RETAIN
6	43+29.8	RIGHT	20.44	692.94	43+11.3	LEFT	27.78	689.30	24" CMP	RETAIN
7	50+18.9	RIGHT	34.70	689.59	50+27.1	LEFT	36.51	686.06	72" CMP	RETAIN
8	60+32.1	RIGHT	19.02	692.42	60+31.7	LEFT	17.84	691.84	15" CMP	RETAIN 51'
9	61+03.6	RIGHT	17.02	692.45	60+80.6	LEFT	16.45	692.23	12" CMP	NEW 18" X 43" CPEP(SL)
<b>BRAINTREE</b>										
10	15+85.7	RIGHT	21.71	680.22	15+89.9	LEFT	22.99	679.63	24" CMP	RETAIN
11	18+55.2	RIGHT	32.08	676.82	18+55.2	LEFT	30.35	676.47	42" CPEP	RETAIN
12	22+45.5	RIGHT	24.60	679.33	22+64.3	LEFT	22.43	678.63	15" CMP	RETAIN
13	40+81.9	RIGHT	18.20	729.17	40+79.7	LEFT	24.20	727.95	18" CMP	RETAIN
14	45+92.9	RIGHT	25.23	725.25	45+90.4	LEFT	26.99	724.42	18" CMP	RETAIN
15	55+10.9	RIGHT	22.46	723.30	55+15.8	LEFT	30.57	719.21	- BR#2-BOX	RETAIN
16	57+28.0	RIGHT	24.74	727.51	57+18.8	LEFT	31.21	725.54	30" CMP	RETAIN
17	64+09.8	RIGHT	22.42	732.30	64+09.2	LEFT	23.70	731.24	18" RCP	RETAIN
18	68+57.8	RIGHT	27.17	739.47	68+47.6	LEFT	32.39	735.49	15" CMP	RETAIN
19	83+80.1	RIGHT	30.61	714.13	83+56.3	LEFT	27.85	713.27	42" CMP	RETAIN
20	89+19.0	RIGHT	28.80	716.61	89+18.8	LEFT	23.46	715.99	74"x153.5" CMP	RETAIN
21	94+00.4	RIGHT	26.21	721.66	94+02.6	LEFT	28.05	720.26	15" RCP	RETAIN
22	95+46.1	RIGHT	24.09	722.41	95+41.5	LEFT	26.33	721.08	18" CMP	RETAIN
23	106+85.1	RIGHT	19.71	748.25	106+85.7	LEFT	26.69	747.58	15" CMP	RETAIN
24	110+96.0	RIGHT	20.35	747.01	110+74.9	LEFT	35.21	741.64	18" CMP	RETAIN
25	118+46.8	RIGHT	28.94	752.88	118+43.2	LEFT	29.21	751.50	72"x63" CMP	RETAIN
26	125+88.9	RIGHT	21.52	745.45	125+84.4	LEFT	41.35	744.02	36" CMP	RETAIN
27	136+98.7	RIGHT	34.83	758.84	136+98.6	LEFT	31.74	756.82	32" CMP	RETAIN
28	154+25.5	RIGHT	21.98	758.75	154+53.7	LEFT	22.56	757.29	15" CMP	RETAIN
29	160+89.5	RIGHT	25.52	760.78	160+88.6	LEFT	33.10	755.52	15" CMP	RETAIN
30	164+91.6	RIGHT	26.91	760.06	164+92.9	LEFT	23.21	758.89	15" RCP	RETAIN
31	197+60.6	RIGHT	39.97	755.27	197+56.5	LEFT	40.56	755.06	18" CPEP	RETAIN
32	210+52.1	LEFT	27.67	761.88	210+52.5	RIGHT	38.59	759.45	18" CPEP	RETAIN
33	218+55.6	LEFT	27.27	765.34	218+63.7	RIGHT	42.51	763.40	30" CMP	RETAIN
34	225+46.8	LEFT	19.76	780.70	225+23.8	RIGHT	23.46	779.41	18" CMP	RETAIN
35	240+00.1	LEFT	17.56	779.65	240+70.1	RIGHT	23.60	778.38	18" CMP	RETAIN
36	246+30.3	RIGHT	28.25	772.31	246+30.2	LEFT	21.19	772.05	24" CMP	RETAIN
37	251+68.5	LEFT	22.11	774.26	251+40.5	RIGHT	24.99	772.58	18" CMP	RETAIN
38	263+82.2	LEFT	20.51	778.70	263+84.2	RIGHT	24.49	778.24	12" CMP	RETAIN
39	275+20.8	LEFT	19.39	787.61	275+00.9	RIGHT	27.66	786.46	18" CMP	RETAIN
40	286+98.0	LEFT	20.07	807.89	287+01.1	RIGHT	30.88	806.76	24" CMP	RETAIN
41	288+69.5	LEFT	19.38	809.49	288+80.8	RIGHT	29.82	808.30	18" CMP	RETAIN
42	296+80.5	LEFT	21.11	809.46	297+03.2	RIGHT	28.20	808.64	15" CMP	RETAIN
43	299+57.1	LEFT	26.53	800.93	299+70.8	RIGHT	45.57	796.38	18" CMP	RETAIN
44	301+86.9	LEFT	32.14	796.56	301+92.6	RIGHT	34.52	790.42	15" CMP	RETAIN
45	303+29.2	LEFT	24.82	796.58	303+30.4	RIGHT	32.58	788.90	15" CMP	RETAIN
46	305+44.9	LEFT	21.50	795.15	305+43.9	RIGHT	34.47	791.09	15" CMP	RETAIN
47	309+16.6	LEFT	18.67	794.28	309+18.9	RIGHT	27.88	792.42	18" CMP	RETAIN
48	311+95.6	LEFT	23.11	798.23	311+98.5	RIGHT	29.65	795.08	18" CMP	RETAIN
49	314+05.2	LEFT	22.22	795.66	314+04.8	RIGHT	24.14	794.17	18" CMP	RETAIN

CULVERT NO.	INVERT IN				INVERT OUT				PIPE	COMMENT
	STATION	POSITION	OFFSET FROM HCL	ELEVATION	STATION	POSITION	OFFSET FROM HCL	ELEVATION		
<b>BRAINTREE (CONT.)</b>										
50	316+42.9	LEFT	19.87	796.51	316+39.3	RIGHT	26.98	796.01	12" CMP	RETAIN
51	335+25.7	LEFT	20.32	811.88	335+42.6	RIGHT	20.94	811.05	18" CMP	RETAIN
52	336+17.0	LEFT	20.56	812.03	336+16.4	RIGHT	25.63	810.21	18" RCP	RETAIN
53	338+20.6	LEFT	19.05	816.65	338+18.4	RIGHT	26.57	815.16	18" RCP	RETAIN
54	342+47.9	LEFT	21.13	835.19	342+44.6	RIGHT	25.47	830.29	24" CMP	RETAIN 7'
55	351+37.3	LEFT	19.18	810.59	351+35.5	RIGHT	42.23	804.73	18" RCP	EXTEND EXISTING 18" RCP -3' LT
56	355+86.4	LEFT	22.05	813.26	355+82.7	RIGHT	41.24	806.96	18" CMP	RETAIN
57	358+59.5	LEFT	18.32	814.10	358+62.2	RIGHT	42.84	807.04	18" RCP	RETAIN
58	361+19.6	LEFT	18.03	814.59	361+23.0	RIGHT	43.90	809.62	18" RCP	RETAIN
59	363+49.3	LEFT	17.35	814.56	363+48.9	RIGHT	42.03	811.61	18" CMP	RETAIN 6'
60	365+83.6	LEFT	14.86	815.52	365+84.8	RIGHT	40.91	810.55	18" CMP	EXTEND EXISTING 18" CMP -4' LT
61	368+74.0	LEFT	18.82	815.24	368+77.1	RIGHT	34.06	811.78	18" CMP	RETAIN
62	371+27.8	LEFT	19.76	814.27	371+23.1	RIGHT	26.98	813.07	24" CMP	RETAIN
63	376+30.7	LEFT	18.41	816.05	376+30.4	RIGHT	21.13	815.58	15" CPEP	RETAIN
<b>GRANVILLE</b>										
64	14+63.5	LEFT	17.54	831.35	14+64.6	RIGHT	20.25	830.35	24" CPEP	EXTEND EXISTING 24" CPEP -3' LT
65	15+92.8	LEFT	18.01	832.55	15+92.8	RIGHT	18.18	831.51	18" CPEP	RETAIN 13.5'
66	19+73.5	LEFT	21.04	840.65	19+36.2	RIGHT	17.28	839.16	18" RCP	EXTEND EXISTING 18" RCP +1.5' RT
67	28+63.9	LEFT	16.66	846.68	28+65.7	RIGHT	23.70	845.65	18" CMP	EXTEND EXISTING 18" CMP -3' LT
68	30+28.7	LEFT	22.02	846.61	30+29.4	RIGHT	24.66	842.09	18" CMP	RETAIN 4.5'
69	34+36.7	LEFT	17.87	851.81	34+36.4	RIGHT	34.74	841.72	18" CMP	RETAIN 5'
70	35+53.0	LEFT	17.03	850.61	35+53.8	RIGHT	34.19	847.46	18" CPEP	EXTEND EXISTING 18" CPEP 4' LT
71	38+08.1	LEFT	17.48	846.88	38+08.4	RIGHT	29.19	842.24	18" CMP	RETAIN
72	39+17.9	LEFT	17.94	846.09	39+17.6	RIGHT	31.48	842.90	18" CMP	RETAIN 48' -----50'
73	41+19.6	LEFT	22.07	848.59	41+20.8	RIGHT	31.03	844.11	18" CMP	NEW 18" X 54" CPEP(SL)
74	46+75.8	LEFT	16.62	857.88	46+77.4	RIGHT	24.89	852.95	15" RCP	NEW 18" X 43" CPEP(SL), CONSTRUCT HEADWALL AT INLET -----53' 7'
75	49+08.1	LEFT	17.38	853.15	49+07.5	RIGHT	28.12	846.93	18" RCP	EXTEND EXISTING 18" RCP 2.5' LT
76	50+73.8	LEFT	15.86	854.48	50+72.8	RIGHT	38.14	845.73	18" CGMP	NEW 18" X 60" CPEP(SL)
77	51+76.9	LEFT	20.54	859.32	51+79.5	RIGHT	32.76	850.99	18"-24" RCP-CPEP	NEW 24" X 54" CPEP(SL)
78	56+56.9	LEFT	18.05	848.95	56+57.3	RIGHT	31.63	845.14	18" CMP	RETAIN 49'
79	58+81.3	LEFT	18.54	849.74	58+81.2	RIGHT	21.90	848.88	18" CPEP	RETAIN
80	61+95.1	LEFT	17.68	850.90	61+95.2	RIGHT	24.53	850.24	15" RCP	RETAIN NEW 18" X 45" CPEP
81	73+08.0	LEFT	16.28	855.21	73+08.6	RIGHT	26.21	853.66	18" CMP	RETAIN
82	74+33.5	LEFT	19.31	855.05	74+34.1	RIGHT	21.01	852.45	15" RCP	NEW 18" X 40" CPEP(SL), CONSTRUCT HEADWALL AT INLET
83	78+56.7	LEFT	23.28	853.67	78+56.5	RIGHT	21.63	852.71	18" RCP	RETAIN
84	81+77.4	LEFT	16.23	855.25	81+76.7	RIGHT	25.94	854.61	12" RCP	RETAIN 7.5'
85	84+00.2	LEFT	14.88	854.78	83+72.5	RIGHT	29.86	853.75	18" CMP	EXTEND EXISTING 18" CMP -3' LT
86	88+16.2	LEFT	35.36	856.81	88+14.7	RIGHT	31.59	854.29	18" CMP	RETAIN
<b>ROXBURY</b>										
87	6+56.0	LEFT	35.21	859.60	6+50.3	RIGHT	33.26	857.60	18" CMP	RETAIN
88	8+08.8	LEFT	29.28	860.07	7+61.4	RIGHT	31.19	857.02	18" CMP	RETAIN
89	9+25.5	LEFT	28.10	859.76	8+81.1	RIGHT	27.41	858.02	18" CMP	RETAIN
90	12+22.8	LEFT	27.28	859.60	11+88.6	RIGHT	32.34	857.91	21" CMP	RETAIN
91	22+32.2	LEFT	33.03	866.36	22+31.2	RIGHT	39.56	863.72	18" CMP	RETAIN
92	24+78.1	LEFT	29.85	866.68	24+62.3	RIGHT	35.02	863.63	18" CMP	RETAIN
93	26+14.2	LEFT	28.22	867.43	26+01.2	RIGHT	33.33	866.06	18" CMP	RETAIN
94	29+79.7	LEFT	27.41	868.97	29+76.4	RIGHT	32.99	865.94	18" CMP	RETAIN
95	32+30.3	LEFT	25.13	872.31	32+31.2	RIGHT	27.35	872.10	42" CMP	RETAIN
96	34+39.6	LEFT	27.74	872.18	34+46.9	RIGHT	31.09			