

QUANTITY SHEET 4

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
				ROADWAY	TRAINING	EROSION CONTROL	RAILROAD	BRIDGE	FULL CE ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS		
				4850						4850		LF	SPECIAL PROVISION (BARRIER FOR TEMPORARY TRAFFIC PROTECTION)	900.640	47					
				1						1		LS	SPECIAL PROVISION (GPS MACHINE CONTROL GRADING)	900.645	-			SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)		
							1			1		LS	SPECIAL PROVISION (RECONSTRUCT RAIL-HIGHWAY CROSSING)(AARDOT 247-488D)	900.645	-	33000	TON	MAINLINE SUPERPAVE BITUMINOUS CONCRETE PAVEMENT ROUNDING		
				1						1		LU	SPECIAL PROVISION (MAINTAINANCE OF RAILROAD TRAFFIC) (N.A.B.I.)	900.650	-	33300	TON	TOTAL		
				175000						175000		SY	SPECIAL PROVISION (COLD/MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	2103					
				2600						2600		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	115			SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE, COLD MIX)		
				175000						175000		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE)	900.675	2103			30625	TON	MAINLINE COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT ROUNDING
				175000						175000		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)	900.675	2104			275	TON	ROUNDING
				5350						5350		TON	SPECIAL PROVISION (AGGREGATE TO MEET COLD MIXED GRADATION)	900.680	40			30900	TON	TOTAL
				25						25		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.			84026	TON	SPECIAL PROVISION (RSB SUPP. AGGREGATE MATERIAL)
				33300						33300		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	300			8432	TON	SUPERELEVATION DEFICIENCY CORRECTION
				30900						30900		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE, COLD MIX)	900.680	275			542	TON	UNDERCUT AREA ROUNDING
				2670						2670		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	77			93000	TON	TOTAL
				490						490		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING)	900.680	4					
				93000						93000		TON	SPECIAL PROVISION (RSB SUPPLEMENTAL AGGREGATE MATERIAL)	900.680	542					
				1450						1450		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	16					
				24400						24400		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT, COLD MIX WITH CEMENT)	900.683	200					
				2155						2155		CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	3					

REV	DESCRIPTION	DATE
1	RECLAIMED STABILIZED BASE SPEC. & UNSUITABLE MATERIAL DETAIL	1-16-2015

PROJECT NAME:	RANDOLPH-ROXBURY
PROJECT NUMBER:	ER STP 0187(II)
FILE NAME:	z13c182frm.dgn
PROJECT LEADER:	M. FOISY
DESIGNED BY:	G. BURGMEIER
QUANTITY SHEET 4	
PLOT DATE:	1/16/2015
DRAWN BY:	G. BURGMEIER
CHECKED BY:	M. FOISY
SHEET	39 OF 545

