STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 15

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
BRAINTREE (CONTINUED)																																				
STA. 285+57, LT	B-B BRIDGE 9 VT 12A	1	~~18~~	~~24~~	~~3.00~~		+				1					X		X																WI-8 WI-8 MOUNT SALVAGED SIGN ON NEW POST	X X		
		1	~~18~~	~~24~~	~~3.00~~																															
STA. 286+37, LT	B-B	1	~~18~~	~~24~~	~~3.00~~						1					X		X																WI-8 WI-8	X X		
		1	~~18~~	~~24~~	~~3.00~~																															
STA. 287+17, LT	B-B	1	~~18~~	~~24~~	~~3.00~~						1					X		X																WI-8 WI-8	X X		
		1	~~18~~	~~24~~	~~3.00~~																															
STA. 289+67, LT	30 MPH	1	30	30	6.25						1					~~15.00~~ X		X																WI-1 WI3-1P	X X		
		1	~~18~~	~~18~~	~~2.25~~																															
STA. 291+67, LT	SOUTH VERMONT 12A	1	24	12	2.00						1					~~13.75~~ X		X																M3-1 (GREEN ON WHITE) (GREEN ON WHITE)	X		E-136B
		1	24	24	4.00																															
STA. 292+15, RT	BRIDGE 10 VT 12A						1				1				X	~~9.00~~ X		X																MOUNT SALVAGED SIGN ON NEW POST			
STA. 292+39, LT	BRIDGE 10 VT 12A						1				1				X	~~8.00~~ X		X																MOUNT SALVAGED SIGN ON NEW POST			
STA. 292+92, RT	LEGAL LOAD LIMIT 24,000 POUNDS SPEED LIMIT 35	1	24	30	5.00						1					~~17.00~~ X								~~1~~	~~X~~									VR-017 R2-1	 X		E-141
		1	24	30	5.00																															
STA. 293+08, RT	STOP 0121 0902 0935 B-B	1	30	30	6.25						1					~~14.25~~ X		X																RI-1 VD-700	X 		 T-44
		1	6	10	0.42																															
STA. 293+10, RT	Thresher Rd						1				1					~~11.75~~ X		X																MOUNT SALVAGED SIGN ON NEW POST			
TOTALS					SF ~~49.17~~ 31.17	SF	EA. ~~4~~ 3	SF				FT 20	FT 85	FT 17	FT ~~122~~ 88.75				EA	LB	LB	LB	EA. 1	LB 130				EA.	EA.	LB					

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: RANDOLPH-ROXBURY
PROJECT NUMBER: ER STP 0187(11)

FILE NAME: z13c182frm.dgn
PROJECT LEADER: M. FOISY
DESIGNED BY: G. BURGMEIER
TRAFFIC SIGN SUMMARY SHEET 15

PLOT DATE: 11/17/2014
DRAWN BY: P. BALASCO
CHECKED BY: M. FOISY
SHEET 194 OF 545