STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 16

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS: EA | WIDTH (In) | HEIGHT (In) | NEW & SALVAGED SIGNS: "A" | "B" | SALV SIGN | SALV TIS | EXIST POST: RETAIN | SALVAGE | NEW SIGN POSTS: NO. OF POSTS | FLANGED CHANNEL lb/ft: 1.12 | 2.0 | 3.0 | SQUARE STEEL (In) lb/ft: 1.88 | 2.42 | 3.35 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (In) lb/ft: 3.0 / 1.3 | 4.0 / 1.7 | 4.0 MOD / 1.7 | TUBULAR STEEL Ø (In) FOUNDATION | 3.0 / 7.6 | 3.5 / 9.0 | 4.0 / 10.8 | 5.0 / 14.6 | W-SHAPE STEEL FTG. SIZE 24" | 30" | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHSM * BOOK | DETAIL ON SHEET NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **BRAINTREE (CONTINUED)** | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| STA. 294+25, RT | NORTH VERMONT 12A | 1<br>1 | 24<br>24 | 12<br>24 | 2.00<br>4.00 | | | | | | 1 | | | | | 16.25 X | | X | | | | | | | | | | | | | | | | M3-1 (GREEN ON WHITE)<br>(GREEN ON WHITE) | X | | <br>E-136B |
| STA. 296+00, LT | Jonesville Rd | 1 | 42 | 12 | 3.50 | | | | | | 1 | | | | | 10.25 X | | X | | | | | | | | | | | | | | | | D3-1 DOUBLE SIDED | | 206 | |
| STA. 296+02, LT | DEAD END | 1 | 30 | 30 | 6.25 | | | | | | 1 | | | | | 13.50 X | | X | | | | | | | | | | | | | | | | W14-1 | X | | |
| STA. 305+33, RT | SPEED LIMIT 50 | | | | | | 1 | | | | 1 | | | | | 14.00 X | | X | | | | | | | | | | | | | | | | MOUNT SALVAGED SIGN ON NEW POST | | | |
| STA. 306+24, LT | 0121 0902 0580 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | X | 8.25 X | | X | | | | | | | | | | | | | | | | VD-700 | | | T-44 |
| STA. 316+80, RT | 0121 0902 0600 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | X | 8.50 X | | X | | | | | | | | | | | | | | | | VD-700 | | | T-44 |
| STA. 324+88, RT | Lemery Rd | 1<br>1 | 36<br>30 | 36<br>8 | 9.00<br>1.67 | | | | | | 2 | | | | | 15.50 X 15.75 | | X | | | | | | | | | | | | | | | | W10-3R<br>W16-8P | X | <br>206 | |
| STA. 327+36, LT | 0121 0902 0620 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | X | 7.25 X | | X | | | | | | | | | | | | | | | | VD-700 | | | T-44 |
| STA. 328+42, RT | BRIDGE 11 VT 12A | 1 | 6 | 8 | 0.33 | | | | | | 1 | | | | X | 7.75 X | | X | | | | | | | | | | | | | | | | VD-701 | | | T-42 |
| STA. 328+88, LT | BRIDGE 11 VT 12A | 1 | 6 | 8 | 0.33 | | | | | | 1 | | | | X | 7.25 X | | X | | | | | | | | | | | | | | | | VD-701 | | | T-42 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| **TOTALS** | | | | | SF 28.34 | SF | EA. 1 | SF | | | | FT | FT | FT | FT 50 | FT 97 | FT ~~147~~ 124.75 | | EA | LB | LB | LB | EA. | LB | LB | LB | LB | EA. | EA. | LB | | | | | | |

*
"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: RANDOLPH-ROXBURY
PROJECT NUMBER: ER STP 0187(11)

FILE NAME: z13c182frm.dgn
PROJECT LEADER: M. FOISY
DESIGNED BY: G. BURGMEIER
**TRAFFIC SIGN SUMMARY SHEET 16**

PLOT DATE: 11/17/2014
DRAWN BY: P. BALASCO
CHECKED BY: M. FOISY
SHEET 195 OF 545