STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 23

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
ROXBURY (CONTINUED)																																				
STA. 35+40, LT		1	12	36	3.00		1				1					11.00 X		X																OM3-L	X		
STA. 35+83, RT	13'-0"	1	36	36	9.00						2					13.00 X		X																WI2-2	X		
SIDE ROADS																																				
MOBILE ACRES STA. 11+17, RT	R R	1	36	36	7.07						1					13.00 X		X																WI0-1 LOCATED ON MOBILE ACRES RAILROAD CROSSING APPROACH. REFER TO SHEET 29	X		
STA. 11+91, RT	RAIL CROSSING ROAD REPORT PROBLEM OR EMERGENCY 1-800-555-5555 X-ING 247 582 S	2 1	48 12	9 9	6.00 0.75																													RI5-1 MOUNT NEW SIGNS ON EXISTING RAILROAD SIGNAL POLE; OVERLAY THE ENTIRE BACK OF THE CROSSBUCK SIGNS WITH REFLECTIVE SHEETING. I-13a	X X		
STA. 12+23, LT	RAIL CROSSING ROAD REPORT PROBLEM OR EMERGENCY 1-800-555-5555 X-ING 247 582 S	2 1	48 12	9 9	6.00 0.75																													RI5-1 MOUNT NEW SIGNS ON EXISTING RAILROAD SIGNAL POLE; OVERLAY THE ENTIRE BACK OF THE CROSSBUCK SIGNS WITH REFLECTIVE SHEETING. I-13a	X X		
STA. 14+06, LT	R R	1	36	36	7.07						1					14.00 X		X																WI0-1 LOCATED ON MOBILE ACRES RAILROAD CROSSING APPROACH. REFER TO SHEET 29	X		
RIFORD BROOK ROAD STA. 21+10, RT	RAIL CROSSING ROAD REPORT PROBLEM OR EMERGENCY 1-800-555-5555 X-ING 247 483 U	2 1	48 12	9 9	6.00 0.75																													RI5-1 MOUNT NEW SIGNS ON EXISTING RAILROAD SIGNAL POLE; OVERLAY THE ENTIRE BACK OF THE CROSSBUCK SIGNS WITH REFLECTIVE SHEETING. I-13a	X X		
STA. 21+53, LT	RAIL CROSSING ROAD REPORT PROBLEM OR EMERGENCY 1-800-555-5555 X-ING 247 483 U	2 1	48 12	9 9	6.00 0.75																													RI5-1 MOUNT NEW SIGNS ON EXISTING RAILROAD SIGNAL POLE; OVERLAY THE ENTIRE BACK OF THE CROSSBUCK SIGNS WITH REFLECTIVE SHEETING. I-13a	X X		
TOTALS		SF 53.14	SF	EA. 1	SF							FT	FT	FT	FT	FT 85	FT 85 51.00		EA	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB						

*
"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: RANDOLPH-ROXBURY
PROJECT NUMBER: ER STP 0187(11)

FILE NAME: zl3cl82frm.dgn
PROJECT LEADER: M. FOISY
DESIGNED BY: G. BURGMEIER
TRAFFIC SIGN SUMMARY SHEET 23

PLOT DATE: 11/17/2014
DRAWN BY: P. BALASCO
CHECKED BY: M. FOISY
SHEET 202 OF 545