STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 24

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
SIDE ROADS (CONTINUED)																																				
STA. 22+28, LT	R R	1	36	36	7.07		1				1					14.00 X		X																WIO-1 LOCATED ON RIFORD BROOK ROAD RAILROAD CROSSING APPROACH. REFER TO SHEET 29	X		
LEMERY ROAD																																				
	RAIL CROSSING ROAD	2	48	9	6.00																													RI5-1 OVERLAY THE ENTIRE BACK OF THE CROSSBUCK SIGNS WITH REFLECTIVE SHEETING.	X		
STA. 30+55, RT	YIELD	1	36 X 36 X 36		3.89						1					17.00 X							I	X									RI-2	X		
	REPORT PROBLEM OR EMERGENCY 1-800-555-5555 X-ING 247 493 A	1	12	9	0.75																													I-13a	X		
	RAIL CROSSING ROAD	2	48	9	6.00																													RI5-1 OVERLAY THE ENTIRE BACK OF THE CROSSBUCK SIGNS WITH REFLECTIVE SHEETING.	X		
STA. 30+92, LT	YIELD	1	36 X 36 X 36		3.89						1					16.25 X							I	X									RI-2	X		
	REPORT PROBLEM OR EMERGENCY 1-800-555-5555 X-ING 247 493 A	1	12	9	0.75																													I-13a	X		
STA. 31+00, LT	R R	1	36	36	7.07						1					13.00 X		X																WIO-1 LOCATED ON LEMERY ROAD RAILROAD CROSSING APPROACH. REFER TO SHEET 30	X		
HANDLY ROAD																																				
	RAIL CROSSING ROAD	2	48	9	6.00																													RI5-1 OVERLAY THE ENTIRE BACK OF THE CROSSBUCK SIGNS WITH REFLECTIVE SHEETING.	X		
STA. 40+45, RT	YIELD	1	36 X 36 X 36		3.89						1					18.00 X							I	X									RI-2	X		
	REPORT PROBLEM OR EMERGENCY 1-800-555-5555 X-ING 247 494 0	1	12	9	0.75																													I-13a	X		
	RAIL CROSSING ROAD	2	48	9	6.00																													RI5-1 OVERLAY THE ENTIRE BACK OF THE CROSSBUCK SIGNS WITH REFLECTIVE SHEETING.	X		
STA. 40+83, LT	YIELD	1	36 X 36 X 36		3.89						1					15.75 X							I	X									RI-2	X		
	REPORT PROBLEM OR EMERGENCY 1-800-555-5555 X-ING 247 494 0	1	12	9	0.75																													I-13a	X		
TOTALS		SF 56.70	SF	EA.	SF				FT	FT	FT	FT	FT 30	FT ~~30~~ 94.00	FT		EA	LB	LB	LB	EA. 4	LB	LB	LB	LB 412	EA.	EA.	LB						

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: RANDOLPH-ROXBURY
PROJECT NUMBER: ER STP 0187(11)

FILE NAME: z13ci82frm.dgn
PROJECT LEADER: M. FOISY
DESIGNED BY: G. BURGMEIER
TRAFFIC SIGN SUMMARY SHEET 24

PLOT DATE: 11/17/2014
DRAWN BY: P. BALASCO
CHECKED BY: M. FOISY
SHEET 203 OF 545