

QUANTITY SHEET 4

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
			ROADWAY	ROADWAY (NON-PART FED)	TRAINING	EROSION CONTROL	RAILROAD	BRIDGE	FULL CE ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						10200				10200		LB	FERTILIZER	651.18	EST.			TEMPORARY EROSION MATTING
						50				50		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
						50				50		TON	HAY MULCH	651.25	EST.			
			5250							5250		CY	TOPSOIL	651.35	EST.			
			4100							4100		SY	GRUBBING MATERIAL (6")	651.40	106			
						9500				9500		SY	TEMPORARY EROSION MATTING	653.20	93			
						2450				2450		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	EST.			
						4				4		EACH	INLET PROTECTION DEVICE, TYPE I	653.40	-			
						15300				15300		LF	BARRIER FENCE	653.50	145			
						20000				20000		LF	PROJECT DEMARCATION FENCE	653.55	EST.			
						14500				14500		LF	EROSION LOG	653.60	EST.			
			1254.55							1254.55		SF	TRAFFIC SIGNS, TYPE A	675.20	-			
			630							630		LB	TUBULAR STEEL SIGN POST	675.33	11			
			4750	125						4875		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	48			
			5							5		EACH	FOUNDATION FOR TUBULAR STEEL POST	675.43	-			
			273	3						276		EACH	REMOVING SIGNS	675.50	-			
			13	3						16		EACH	ERECTING SALVAGED SIGNS	675.60	-			
			100							100		EACH	DELINEATOR WITH STEEL POST	676.10	4			
			80							80		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	2			
			1							1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
			1							1		EACH	SPECIAL PROVISION (CORING CONCRETE)	900.620	-			
			14							14		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620	EST.			
			1							1		EACH	SPECIAL PROVISION (GNSS CONSTRUCTION INSPECTION EQUIPMENT)	900.620	-			
			170							170		LF	SPECIAL PROVISION (BAND JOINT @ RAILROAD CROSSING)	900.640	6			
			18500							18500		LF	SPECIAL PROVISION (BARRIER FOR TEMPORARY TRAFFIC PROTECTION)	900.640	395			
			1							1		LS	SPECIAL PROVISION (GPS MACHINE CONTROL GRADING)	900.645	-			
							1			1		LU	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC) (N.A.B.I.)	900.650	-			
			61100							61100		SY	SPECIAL PROVISION (COLD-MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	575			
			90000							90000		SY	SPECIAL PROVISION (FULL DEPTH RECLAMATION, EMULSIFIED ASPHALT)	900.675	710			
			2750							2750		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	43			
			86800							86800		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE)	900.675	843			
			2100							2100		TON	SPECIAL PROVISION (AGGREGATE TO MEET COLD MIXED GRADATION)	900.680	21			
			19600							19600		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	200			
			12600							12600		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE, COLD MIX)	900.680	125			
			100							100		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIXED RECYCLING)	900.680	1			
			255							255		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR FULL DEPTH RECLAMATION, EMULSIFIED ASPHALT)	900.680	4			
			15200							15200		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT FOR FULL DEPTH RECLAMATION)	900.683	152			
			6500							6500		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT, COLD MIX WITH CEMENT)	900.683	100			
			1120							1120		CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	8			

PROJECT NAME: ROXBURY-NORTHFIELD
 PROJECT NUMBER: ER STP 0187(13)
 FILE NAME: z13c184frm.dgn PLOT DATE: 6/21/2016
 PROJECT LEADER: M. FOISY DRAWN BY: G. BURGMEIER
 DESIGNED BY: G. BURGMEIER CHECKED BY: G. EDWARDS
QUANTITY SHEET 4 SHEET 21 OF 476

