STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
ROXBURY (CONT.)																																				
STA. 266+43, LT	SPEED LIMIT 35	1	30	36	7.50						1						X	X															R2-1	X		
STA. 269+34, LT	Roxbury E. Granville 6	1	30	18	3.75						1					X		X															VD-018		191	
STA. 270+45, RT	Northfield 6	1	72	12	6.00						2					X		X															VD2-1			T-93
STA. 274+56, RT	0121 1215 0520	1	6	10	0.42						1				X			X															VD-700			T-44
STA. 275+76, RT	Ellis Rd	1	36	36	9.00						2					X		X															W10-3L	X		
		1	24	8	1.33																												W16-8P		190	
STA. 276+08, LT	SPEED LIMIT 35	1	36	36	9.00						2					X		X															W3-5	X		
STA. 278+00, LT	SUMMER CAMP AREA	1	30	30	6.25						1						X	X															DETAILED SIGN		191	
STA. 278+92, LT	STOP 0121 1215 0528 B-B	1	30	30	6.25						1					X		X															RI-1	X		
		1	6	10	0.42																												VD-700			T-44
STA. 279+28, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X															VR-017			T-70
STA. 279+47, LT	Ellis Rd	1	30	12	2.50						1					X		X															D3-1 DOUBLE SIDED		189	
STA. 278+94, LT	DO NOT STOP ON TRACKS	1	24	30	5.00						1					X		X															R8-8	X		
												FT	FT	FT	FT 10	FT 186	FT 40		EA	LB	LB	LB		LB	LB	LB	LB									
TOTALS					SF 62.42	SF	EA.	SF				FT			FT 236					LB			EA.	LB				EA.	EA.	LB						

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: ROXBURY-NORTHFIELD
PROJECT NUMBER: ER STP 0187(13)

FILE NAME: z13c184typ.dgn
PROJECT LEADER: M. FOISY
DESIGNED BY: G. BURGMEIER
TRAFFIC SIGN SUMMARY SHEET 11

PLOT DATE: 6/13/2016
DRAWN BY: G. BARRETT
CHECKED BY: G. EDWARDS
SHEET 172 OF 476