STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
ROXBURY (CONT.)																																				
STA. 325+00, LT	TRUCKS ENTERING	1	36	36	9.00						2					X		X																VW-202			T-81
STA. 327+36, RT	0121 1215 0620	1	6	10	0.42						1				X			X																VD-700			T-44
NORTHFIELD																																				
ROXBURY 327+77.95, LT= NORTHFIELD 0+00, LT	Roxbury | Northfield	1	72	10	5.00						2					X		X																VD-024			T-94
	0121 1215 0621	1	6	10	0.42																													VD-700			T-44
	0121 1213 0000	1	6	10	0.42																													VD-700			T-44
STA. 1+80, RT		1	30	30	6.25						1						X	X																W2-2R	X		
	Evans Rd	1	24	8	1.33																													W16-8P		190	
STA. 2+45, LT	Rabbit Hollow Rd	1	60	12	5.00						2					X		X																D3-1 DOUBLE SIDED		189	
STA. 2+54, LT	STOP 0121 1213 0005 B-B	1	30	30	6.25						1					X		X																RI-1	X		
		1	6	10	0.42																													VD-700			T-44
STA. 2+86, LT	LEGAL LOAD LIMIT 16,000 POUNDS	1	24	30	5.00						1						X	X																VR-017			T-70
	SPEED LIMIT 30	1	24	30	5.00																													R2-1	X		
STA. 4+88, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X																VR-017			T-70
STA. 5+23, RT	STOP 0121 1213 0010 B-B	1	30	30	6.25						1					X		X																RI-1	X		
		1	6	10	0.42																													VD-700			T-44
STA. 5+30, LT		1	30	30	6.25						1						X	X																W2-2R	X		
	Rabbit Hollow Rd	1	30	15	3.13																													W16-8aP		190	
STA. 5+31, RT	Evans Rd	1	36	12	3.00						1					X		X																D3-1 DOUBLE SIDED		189	
												FT	FT	FT	FT 10	FT 172	FT 53		EA	LB	LB	LB		LB	LB	LB	LB									
TOTALS					SF 68.56	SF	EA.	SF				FT			FT 235					LB			EA.	LB				EA.	EA.	LB						

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: ROXBURY-NORTHFIELD
PROJECT NUMBER: ER STP 0187(13)

FILE NAME: z13ci84typ.dgn
PROJECT LEADER: M. FOISY
DESIGNED BY: G. BURGMEIER
TRAFFIC SIGN SUMMARY SHEET 13

PLOT DATE: 6/13/2016
DRAWN BY: G. BARRETT
CHECKED BY: G. EDWARDS
SHEET 174 OF 476