STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 26

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (In) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
SIDEROADS (CONT.)															1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6									
CARRIE HOWE RD																																				
STA. 40+56, LT	RAIL ROAD CROSSING	2	48	9	6.00																													RI5-1 OVERLAY THE ENTIRE BACK OF THE CROSSBUCK SIGNS WITH REFLECTIVE SHEETING.	X		
	YIELD	1	36 X 36 X 36		3.89						1												1	117									RI-2	X		
	REPORT PROBLEM OR EMERGENCY 1-800-800-3490 X-ING 247 498 J	1	12	9	0.75																													I-13a	X		
WARREN MTN RD																																				
STA. 71+56, RT	RAIL ROAD CROSSING 2 TRACKS	2	48	9	6.00				1																									RI5-1 MOUNT SIGNS ON EXISTING SIGNAL ASSEMBLY	X		
		1	(9X9+9X27)		2.25																													RI5-2P	X		
	REPORT PROBLEM OR EMERGENCY 1-800-800-3490 X-ING 247 499 R	1	12	9	0.75																													I-13a	X		
STA. 71+64, LT	RAIL ROAD CROSSING 2 TRACKS	2	48	9	6.00				1																									RI5-1 MOUNT SIGNS ON EXISTING SIGNAL ASSEMBLY	X		
		1	(9X9+9X27)		2.25																													RI5-2P	X		
	REPORT PROBLEM OR EMERGENCY 1-800-800-3490 X-ING 247 499 R	1	12	9	0.75																													I-13a	X		
STA. 70+57, RT	R R	1	36	36	7.07						1					X		X																WI0-1 LOCATED ON WARREN MOUNTAIN ROAD RAILROAD CROSSING APPROACH. REFER TO SHEET 49	X		
STA. 74+10, LT	R R	1	36	36	7.07						1					X		X																WI0-1 LOCATED ON WARREN MOUNTAIN ROAD RAILROAD CROSSING APPROACH. REFER TO SHEET 49	X		
ELLIS ROAD STA. 80+33, RT	RAIL ROAD CROSSING	2	48	9	6.00				1																									RI5-1 MOUNT NEW SIGNS ON EXISTING RAILROAD SIGNAL POLE; OVERLAY THE ENTIRE BACK OF THE CROSSBUCK SIGNS WITH REFLECTIVE SHEETING.	X		
	REPORT PROBLEM OR EMERGENCY 1-800-800-3490 X-ING 247 501 P	1	12	9	0.75																													I-13a	X		
												FT	FT	FT	FT	FT 30	FT		EA	LB	LB	LB		LB 117	LB	LB	LB								
TOTALS					SF 49.53	SF	EA.	SF				FT			FT 30					LB			EA. 1	LB 117				EA.	EA.	LB					

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: ROXBURY-NORTHFIELD
PROJECT NUMBER: ER STP 0187(13)

FILE NAME: z13c184typ.dgn
PROJECT LEADER: M. FOISY
DESIGNED BY: G. BURGMEIER
TRAFFIC SIGN SUMMARY SHEET 26

PLOT DATE: 5/25/2016
DRAWN BY: G. BARRETT
CHECKED BY: G. EDWARDS
SHEET 187 OF 476