



4 EACH

E ANCHOR BAR SCHEDULE (EPOXY)

PART	MARK	QTY	SIZE	SPC	LENGTH	TYPE	A	B	C	D
ANCHOR (E)	A601E	1	#6	0"	174"	TYP1	5"	72"	6"	6"
ANCHOR (E)	A602E	1	#6	0"	190"	TYP1	5"	80"	6"	6"
ANCHOR (E)	A603E	1	#6	0"	206"	TYP1	5"	88"	6"	6"
ANCHOR	A504	2	#5	0"	56"	TYP2	12"	44"	0"	0"
ANCHOR (E)	A505	8	#5	12"	38"	STR				
ANCHOR	A506	4	#5	VAR.	50"	STR	0"	0"	0"	0"
ANCHOR	A507	7	#5	8"	26"	STR	0"	0"	0"	0"
ANCHOR (E)	A608E	1	#6	0"	198"	TYP1	6"	84"	6"	6"

CUBIC YARDS = .64 WEIGHT = 1.3 TONS

NOTE: ALL BAR COVER 2" UNLESS NOTED OTHERWISE

1 EACH

F ANCHOR BAR SCHEDULE (EPOXY)

PART	MARK	QTY	SIZE	SPC	LENGTH	TYPE	A	B	C	D
ANCHOR (F)	A601E	1	#6	0"	198"	TYP1	6"	84"	6"	6"
ANCHOR (F)	A602E	1	#6	0"	214"	TYP1	6"	92"	6"	6"
ANCHOR (F)	A603E	1	#6	0"	230"	TYP1	6"	100"	6"	6"
ANCHOR	A504	2	#5	0"	56"	TYP2	12"	44"	0"	0"
ANCHOR (F)	A505	10	#5	12"	38"	STR				
ANCHOR	A506	4	#5	VAR.	50"	STR	0"	0"	0"	0"
ANCHOR	A507	7	#5	8"	26"	STR	0"	0"	0"	0"
ANCHOR (F)	A608E	1	#6	0"	222"	TYP1	6"	96"	6"	6"

CUBIC YARDS = .71 WEIGHT = 1.43 TONS

NOTE: ALL BAR COVER 2" UNLESS NOTED OTHERWISE



5/8/18

PREPARED BY: 860 HOOPER ROAD, ENDWELL, NY 13760 TEL: (607) 231-6600 FAX: (607) 231-6650		PREPARED FOR: CAMP PRECAST CONCRETE PRODUCTS 78 PRECAST RD MILTON, VT 05468 PHONE: (802)893-2401 FAX: (802)893-1542	
REV. NO. DATE REVISION		DATE: 3/29/18 SHEET TITLE: ANCHOR DETAILS DRWN BY: BJC SCALE: N.T.S. CKD BY: RJA	
PROJECT:		WATERFORD, VT 16' x 8' BOX CULVERT BF 0225(5) VT RT. 18 BRIDGE #2	
CONTRACTOR:		DWG. I.D. PD-01	
DELTA PROJ. NO.: 2018.477.003		SHT. NO. 10 OF 13	