

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL CE	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			
								3000			3000		CY	COMMON EXCAVATION	203.15	51			ITEM 900.680 SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)
								600			600		CY	SOLID ROCK EXCAVATION	203.16	10			TYPE IIS TRENCH PATCH
								2030			2030		CY	CHANNEL EXCAVATION OF EARTH	203.25	22	24.2	T	
								590			590		CY	CHANNEL EXCAVATION OF ROCK	203.26	11			TYPE IIS TRENCH PATCH
								1380			1380		CY	TRENCH EXCAVATION OF EARTH	204.20	16.7			TYPE IIS TRENCH PATCH
								130			130		CY	TRENCH EXCAVATION OF ROCK	204.21	11.4	365.9	T	TYPE IIS WEARING COURSE SHIM
								10			10		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST	122	T	
								31			31		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	1.8	24.9	T	ROUNDING
								4300			4300		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	20.1	560	T	TOTAL
								16			16		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	0.3			
								80			80		TON	AGGREGATE SHOULDERS, RAP	402.13	0.1			
														BEGIN OPTION AA					
								29			29		CWT	EMULSIFIED ASPHALT	404.65	0.5			
								29			29		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	0.5			
														END OPTION AA					
								1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
														BEGIN OPTION BB					
								45			45		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215	0.5			
								45			45		LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415	0.5			
								45			45		LF	18" CPEP	601.0915	0.5			
														END OPTION BB					
								16			16		LF	18" PCCSP(PI) .064 (2-2/3 X 1/2)	601.0615	-			
								4			4		LF	24" CPEP(SL)	601.2620	-			
								4			4		LF	30" CPEP(SL)	601.2625	-			
								1300			1300		LF	6 INCH UNDERDRAIN PIPE	605.10	30			
								50			50		LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20	2			
									2700		2700		CY	STONE FILL, TYPE II	613.11	23			
								12			12		EACH	YIELDING MARKER POSTS	619.17	-			
								1600			1600		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	8			
								2			2		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
								1530			1530		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	4.2			
								800			800		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
								2000			2000		HR	FLAGGERS	630.15	EST			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
								1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
								3			3		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
								3300			3300		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	100			

PROJECT NAME: PLYMOUTH  
PROJECT NUMBER: ER 0149(6)

FILE NAME: z13c318qyl.dgn  
PROJECT LEADER: J. SANTACRUCE  
DESIGNED BY: J. SANTACRUCE  
QUANTITY SHEET I

PLOT DATE: 5/17/2016  
DRAWN BY: J. SANTACRUCE  
CHECKED BY: B. COLBURN  
SHEET II OF 68

