

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL CE	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								3300			3300		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	100			
								9			9		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-			
								120			120		EACH	LINE STRIPING TARGETS	646.76	-			
									515		515		SY	GEOTEXTILE UNDER STONE FILL	649.31	2.5			
									12		12		LB	SEED	651.15	1.1			
									50		50		LB	FERTILIZER	651.18	4.7			
									0.2		0.2		TON	AGRICULTURAL LIMESTONE	651.20	-			
									0.2		0.2		TON	HAY MULCH	651.25	-			
									10		10		CY	TOPSOIL	651.35	1.8			
									300		300		SY	GRUBBING MATERIAL	651.40	10.1			
									1		1		LS	EPSC PLAN	652.10	-			
									50		50		HR	MONITORING EPSC PLAN	652.20	EST			
									1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
									100		100		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	10.6			
									5		5		EACH	PREFABRICATED CHECK DAM	653.30	-			
									7		7		EACH	INLET PROTECTION DEVICE, TYPE I	653.40	-			
									2700		2700		LF	PROJECT DEMARCATION FENCE	653.55	56.1			
									700		700		LF	EROSION LOG	653.60	21.4			
									95.8		95.8		SF	TRAFFIC SIGNS, TYPE A	675.20	-			
									200		200		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	16.5			
									17		17		EACH	REMOVING SIGNS	675.50	-			
									18		18		EACH	DELINEATOR WITH STEEL POST	676.10	-			
									1		1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
									1500		1500		CY	SPECIAL PROVISION (EROSION STONE)	900.608	81			
									8		8		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620	-			
									7		7		EACH	SPECIAL PROVISION (PRECAST CONCRETE CATCH BASIN WITH BEEHIVE CAST IRON GRATE)	900.620	-			
									1		1		EACH	SPECIAL PROVISION (ROCK ANCHOR TESTING)	900.620	-			
									2200		2200		LF	SPECIAL PROVISION (ROCK ANCHORS)	900.640	-			
									1		1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL INCLUSIVE)	900.645	-			
									1		1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650	-			
									1		1		LU	SPECIAL PROVISION (MXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650	-			
									18000		18000		SF	SPECIAL PROVISION (WIRE MESH SLOPE STABILIZATION SYSTEM)	900.670	-			
									560		560		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	24.9			

PROJECT NAME: PLYMOUTH
PROJECT NUMBER: ER 0149(6)

FILE NAME: z13c318qy2.dgn
PROJECT LEADER: J. SANTACRUCE
DESIGNED BY: J. SANTACRUCE
QUANTITY SHEET 2

PLOT DATE: 5/17/2016
DRAWN BY: J. SANTACRUCE
CHECKED BY: B. COLBURN
SHEET 12 OF 68

