

QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

GENERAL ROADWAY	TRAINING	FULL C.E. ITEMS	CHESTER				SPRINGFIELD		ROCKINGHAM	WINDSOR			TOTAL	UNIT	DESCRIPTIONS	ITEM NUMBER	ROUND
			ROADWAY	ROADWAY (NON PART.)	RAIL BID ITEMS	BRIDGE	ROADWAY	BRIDGE	ROADWAY	ROADWAY	BRIDGE						
										I		I	LS	TRAFFIC CONTROL (WINDSOR)	641.10	-	
			3				3	2	3			II	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-	
			2810 29800	1621 1700			25034 23800	18279 19500	44131 45700	117166		120500	LF	DURABLE 4 INCH WHITE LINE, TYPE A TAPE	646.40II	535.0	
			27337 27500	1588 1900			33613 33300	15677 17400	42816 44300	121031		124400	LF	DURABLE 4 INCH YELLOW LINE, TYPE A TAPE	646.41II	349.0	
							12942 21300			12942		21300	LF	DURABLE 6 INCH WHITE LINE, TYPE A TAPE	646.42II	10.0	
			1034 1190				850.4 2280	1326 1060	2439.1 5970	5649.5		10500	LF	DURABLE 8 INCH WHITE LINE, TYPE A TAPE	646.44II	39.0	
				110			2115 1810	354 300	42 80	2621		2300	LF	DURABLE 8 INCH YELLOW LINE, TYPE A TAPE	646.45II	20.0	
			315.5 260	11 40			437.6 460	331 350	383.5 450	1478.6		1560	LF	DURABLE 24 INCH STOP BAR, TYPE A TAPE	646.48II	37.0	
			89	4			204 218	179 180	83 91	559		582	EACH	DURABLE LETTER OR SYMBOL, TYPE D TAPE	646.4914	-	
			863 870				1574.4 1480	1358 1320	1135 1270	4903.4		4940	LF	DURABLE CROSSWALK MARKING, TYPE A TAPE	646.50II	17.0	
			2									2	EACH	DURABLE RAILROAD CROSSING SYMBOL, TYPE D TAPE	646.5114	-	
			25077 59300	2006 3300			49055 47500	15657 38900	41197 91300	133992		240300	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	370.0	
			49336 55000	3727.4 3700			49393 66600	29457 34700	68054 88500	199967.4		248500	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	398.0	
							0 42600			0		42600	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	20.0	
			348.5 510	44.5 70			420 910	630 700	574.5 830	2017.5		3020	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	34.0	
			66 178	4 8			177 436	136 360	88 174	471		1156	EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-	
			1535.7 1740				1486 2960	1982 2640	1238 2530	6241.7		9870	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	24.0	
			4									4	EACH	TEMPORARY RAILROAD CROSSING SYMBOL, PAINT	646.712	-	
			238 1330	0 110			225 1500	266 800	33 2220	762		5960	EACH	LINE STRIPING TARGETS	646.76	30.0	
							1566 910			1566		910	LF	PAINTED CURB	646.81	42.0	
			0 60				52.5 70			52.5		130	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	4.0	
				1198.35 1250						1198.35		1250	SY	GEOTEXTILE UNDER RAILROAD BALLAST	649.21	22.0	
			88.32 45	0 5			30 50	20 50	168 50	306.32		200	LB	SEED	651.15	EST.	
			503.5 450	0 50			132.5 500	125 500	1006 500	1767		2000	LB	FERTILIZER	651.18	EST.	
			1.512 1.8	0 0.2			0.625 2	0.5 2	4.1 2	6.737		8	TON	AGRICULTURAL LIMESTONE	651.20	EST.	
			1.675 1.8	0 0.2			0.5 2	0.5 2	4 2	6.675		8	TON	HAY MULCH	651.25	EST.	
			2.2 45	0 5			3.5 50	13.7 50	3 50	22.4		200	CY	TOPSOIL	651.35	EST.	
									0 230	0		230	SY	TEMPORARY EROSION MATTING	653.20	8.0	

QUANTITY SHEET #3	PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
	PROJECT NUMBER: STP 2952(1)
	FILE NAME: z13c518compqty.dgn PROJECT LEADER: D. GOZALKOWSKI DESIGNED BY: A. HAWKINS
	PLOT DATE: 4/1/2015 DRAWN BY: A. KIRBY CHECKED BY: J. SHIELDS SHEET 9 OF 309