

CHESTER QUANTITY SHEET 4

STATE OF VERMONT
AGENCY OF TRANSPORTATION

ROADWAY VT. ROUTE II	ROADWAY VT. ROUTE 103	ROADWAY (NON PART.)	RAIL BID ITEMS	BRIDGE	TOTALS		UNIT	DESCRIPTIONS ITEMS	ITEM NUMBER	ROUND	DETAILED SUMMARY OF QUANTITIES		
					GRAND TOTAL	FINAL					QUANTITIES	UNIT	ITEMS
			40		40		EACH	SPECIAL PROVISION (REMOVAL AND REPLACEMENT OF CROSS TIES) (9'-0" TIES)	900.620	-			
2					2		EACH	SPECIAL PROVISION (SOLAR-POWERED SCHOOL ZONE FLASHING BEACON)	900.620	-			
			270		270		LF	SPECIAL PROVISION (BAND JOINT @ PRECAST CONCRETE RAILROAD CROSSING)	900.640	-			
			1400		1400		LF	SPECIAL PROVISION (CONTINUOUS WELDED RAIL)	900.640	33.0			
			1300		1300		LF	SPECIAL PROVISION (RAISE, ALIGN, AND SURFACE TRACK)	900.640	100.0			
			1		1		LS	SPECIAL PROVISION (PRECAST CONCRETE PANEL GRADE CROSSING SURFACE) (MAINLINE-AARDOT 859-813N)	900.645	-			
			1		1		LS	SPECIAL PROVISION (PRECAST CONCRETE PANEL GRADE CROSSING SURFACE) (SIDING-AARDOT 859-813N)	900.645	-			
			1		1		LS	SPECIAL PROVISION (RAIL-HIGHWAY CROSSING ACTIVE WARNING SYSTEM) (AARDOT 859-813N)	900.645	-			
			1		1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, RAIL-HIGHWAY CROSSING) (AARDOT 859-813N)	900.645	-			
			1		1		LU	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC) (N.A.B.I.)	900.650	-			
1310	1520	240			3070		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	20.0			
10	15	10			35		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE II)	900.680	EST.			
			1800		1800		TON	SPECIAL PROVISION (RAILROAD BALLAST)	900.680	58.0			
200	300	20	10		530		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-IH OR CRS-IH)	900.683	15.0			

CHESTER QUANTITY SHEET #4	PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
	PROJECT NUMBER: STP 2952(1)
	FILE NAME: z13c518qty_seg01.dgn
	PLOT DATE: 4/1/2015
	DRAWN BY: A. KIRBY
	CHECKED BY: J. SHIELDS
	DESIGNED BY: A. HAWKINS
	SHEET 24 OF 309