

CHESTER ITEM DETAIL SUMMARY SHEET #1

LOCATION			GUARDRAIL				SIDEWALK						MISCELLANEOUS						REMARKS			
BEGIN STATION	END STATION	POS.	621.20	621.216	621.60	621.80	203.15	203.30	301.28	616.21	616.40	618.10	618.30	604.40	604.412	604.415	604.418	604.42		629.20	676.10	
			S.B. GR GALV.	HD S.B GR. GALV., NESTED	ANCHOR FOR S.B. RAIL	REM. & DIS. OF GR	COM. EXCAV.	EARTH BORROW	S.B. OF C.G., F.G.	VERT. GRAN. CURB	REMOVING AND RESETTING CURB	P.C.C. SW. 5 INCH	DET. WARN. SUR.	CHANGING ELEV. OF DI, CB, OR MH	REHAB. DI'S, CB'S, OR MH'S			CHANGING ELEV. OF SEWER MH		ADJUST ELEV. OF VALVE BOX	DEL. W/ ST. POST	
			LF	LF	EA	LF	CY	CY	TON	LF	LF	SY	SF	EA	EA	EA	EA	EA	EA	EA		
CHESTER																						
VT. ROUTE II:																						
C 230+68.32	C 275+56.32	LT/RT												3	13	2	2	15	15		SHALL BE PERFORMED AS DIRECTED BY THE ENGINEER.	
C 230+68.3		LT					0.8		1.0			2.8	10.0								CONSTRUCT LEVEL LANDING W/ DETECTABLE WARNING SURFACE. SEE VTRANS STD SHEET C-3A.	
C 231+13.0		LT					0.8		1.0			2.8	10.0								CONSTRUCT LEVEL LANDING W/ DETECTABLE WARNING SURFACE. SEE VTRANS STD SHEET C-3A.	
C 239+93.0		LT					0.8		1.0			2.8	10.0								CONSTRUCT LEVEL LANDING W/ DETECTABLE WARNING SURFACE. SEE VTRANS STD SHEET C-3A.	
C 239+93.0		RT					0.8		1.0			2.8	10.0								CONSTRUCT LEVEL LANDING W/ DETECTABLE WARNING SURFACE. SEE VTRANS STD SHEET C-3A.	
C 248+41.0		LT					0.8		1.0			2.8	10.0								CONSTRUCT LEVEL LANDING W/ DETECTABLE WARNING SURFACE. SEE VTRANS STD SHEET C-3A.	
C 249+08.0		LT					0.8		1.0			2.8	10.0								CONSTRUCT LEVEL LANDING W/ DETECTABLE WARNING SURFACE. SEE VTRANS STD SHEET C-3A.	
C 251+07.0		LT					0.8		1.0			2.8	10.0								CONSTRUCT LEVEL LANDING W/ DETECTABLE WARNING SURFACE. SEE VTRANS STD SHEET C-3A.	
C 251+11.0		RT					0.8		1.0			2.8	10.0								CONSTRUCT LEVEL LANDING W/ DETECTABLE WARNING SURFACE. SEE VTRANS STD SHEET C-3A.	
C 251+45.0		RT					0.8		1.0			2.8	10.0								CONSTRUCT LEVEL LANDING W/ DETECTABLE WARNING SURFACE. SEE VTRANS STD SHEET C-3A.	
C 257+16.0		LT					3.0	2.0		14.0											REMOVE SIDEWALK RAMP AND INSTALL CURB SEE SHEET 17 FOR SIDEWALK RAMP REMOVAL DETAILS	
C 257+16.0		RT					10.0	19.0		28.0											REMOVE SIDEWALK RAMP AND INSTALL CURB SEE SHEET 17 FOR SIDEWALK RAMP REMOVAL DETAILS	
C 258+11.0		LT					3.2		3.5		14.0	10.6	10.0								CONSTRUCT SIDEWALK RAMP, TYPE 2 W/ DETECTABLE WARNING SURFACE	
C 258+11.0		RT					0.8		1.0		14.0	2.8	10.0								CONSTRUCT LEVEL LANDING W/ DETECTABLE WARNING SURFACE. SEE VTRANS STD SHEET C-3A.	
C 261+35.0		LT					3.2		3.5		14.0	10.6	10.0								CONSTRUCT SIDEWALK RAMP, TYPE 2 W/ DETECTABLE WARNING SURFACE	
C 261+36.0		RT					0.8		1.0			2.8	10.0								CONSTRUCT LEVEL LANDING W/ DETECTABLE WARNING SURFACE. SEE VTRANS STD SHEET C-3A.	
C 265+88.0		RT					3.2		3.5		14.0	10.6	10.0								CONSTRUCT SIDEWALK RAMP, TYPE 6 W/ DETECTABLE WARNING SURFACE	
C 265+88.0		LT					4.9		5.4		14.0	16.1	20.0								CONSTRUCT SIDEWALK RAMP, TYPE 3 W/ DETECTABLE WARNING SURFACE	
C 266+32.0		LT					2.1		2.2		14.0	6.7	10.0								CONSTRUCT SIDEWALK RAMP, TYPE 1 W/ DETECTABLE WARNING SURFACE	
C 269+73.0		LT					3.2		3.5		14.0	10.6	10.0								CONSTRUCT SIDEWALK RAMP, TYPE 6 W/ DETECTABLE WARNING SURFACE	
C 269+86.0		RT					3.2		3.5		14.0	10.6	20.0								CONSTRUCT SIDEWALK RAMP, TYPE 6 W/ DETECTABLE WARNING SURFACE	
C 270+37.0		RT					2.1		2.2		14.0	6.7	10.0								CONSTRUCT SIDEWALK RAMP, TYPE 1 W/ DETECTABLE WARNING SURFACE	
THIS SHEET SUBTOTAL:			-	-	-	-	46.9	21.0	38.3	42.0	126.0	113.3	210.0	3	13	2	2	15	15	-		

CHESTER ITEM DETAIL SUMMARY SHEET #1	PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
	PROJECT NUMBER: STP 295210
	FILE NAME: z13c5181ds_seg01.dgn
PROJECT LEADER: D. GOZALKOWSKI	PLOT DATE: 3/27/2015
DESIGNED BY: A. HAWKINS	DRAWN BY: A. KIRBY
	CHECKED BY: J. SHIELDS
	SHEET 25 OF 309