STATE OF VERMONT
AGENCY OF TRANSPORTATION

CHESTER TRAFFIC SIGN SUMMARY SHEET 13

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR STEEL Ø (In) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
CHESTER VT. ROUTE 103: C 150+61.0, RT	WEST NORTH	1 1	24 24	12 12	2.00 2.00						2					X		X										*2A	SIGN ID CODE M3-4, GREEN ON WHITE SIGN ID CODE M3-1, GREEN ON WHITE	X X		
	VERMONT 11 VERMONT 103	1 1	24 30	24 24	4.00 5.00																									SIGN ID CODE MI-5, GREEN ON WHITE SIGN ID CODE MI-5, GREEN ON WHITE			E-136B E-136B
		1 1	21 21	15 15	2.19 2.19																									SIGN ID CODE M6-3, GREEN ON WHITE SIGN ID CODE M6-1R, GREEN ON WHITE	X X		
C 151+23.0, LT	EAST SOUTH	1 1	24 24	12 12	2.00 2.00						2					X		X										*1A	SIGN ID CODE M3-2, GREEN ON WHITE SIGN ID CODE M3-3, GREEN ON WHITE	X X		
	VERMONT 11 VERMONT 103	1 1	24 30	24 24	4.00 5.00																									SIGN ID CODE MI-5, GREEN ON WHITE SIGN ID CODE MI-5, GREEN ON WHITE			E-136B E-136B
C 151+85.0, LT	EAST SOUTH WEST	1 1 1	24 24 24	12 12 12	2.00 2.00 2.00						2						X	X										*3B	SIGN ID CODE M3-2, GREEN ON WHITE SIGN ID CODE M3-3, GREEN ON WHITE SIGN ID CODE M3-4, GREEN ON WHITE	X X X		
	VERMONT 11 VERMONT 103 VERMONT 11	1 1 1	24 30 24	24 24 24	4.00 5.00 4.00																									SIGN ID CODE MI-5, GREEN ON WHITE SIGN ID CODE MI-5, GREEN ON WHITE SIGN ID CODE MI-5, GREEN ON WHITE			E-136B E-136B E-136B
		1 1 1	21 21 21	15 15 15	2.19 2.19 2.19																									SIGN ID CODE M6-1L, GREEN ON WHITE SIGN ID CODE M6-1L, GREEN ON WHITE SIGN ID CODE M6-1R, GREEN ON WHITE	X X X		
C 152+36.0, LT	Maple St STOP 1030 1407 0289	1	30	8	1.67						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1. TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		84	
		1 1	30 6	30 10	6.25 0.42																									BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700	X		T-44
C 152+65.0, RT	NORTH	1	24	12	2.00						1					X		X												SIGN ID CODE M3-1, GREEN ON WHITE	X		
	VERMONT 103	1	30	24	5.00																									SIGN ID CODE MI-5, GREEN ON WHITE			E-136B
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."											LF	LF	LF	LF	LF 84	LF 28	EA		EA.	LB	LB	LB	LB	EA.	EA.	LB						
	TOTALS				SF 71.29	SF	EA.	SF			LF				LF 112				EA.	LB				EA.	EA.	LB						

CHESTER TRAFFIC SIGN SUMMARY SHEET #13

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(1)

FILE NAME: z13c518tss_seg01.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS
PLOT DATE: 3/27/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 71 OF 309