STATE OF VERMONT
AGENCY OF TRANSPORTATION

CHESTER TRAFFIC SIGN SUMMARY SHEET 16

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR STEEL Ø (In) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
CHESTER VT. ROUTE 103, C 165+42.0, LT	Coach Rd / Depot St / STOP / 1030 1407 0314	1	30	8	1.67						1					X		X											DOUBLE SIDED SIGN, SIGN ID CODE D3-1		84	
		1	30	8	1.67																								DOUBLE SIDED SIGN, SIGN ID CODE D3-1. TWO TOP MOUNTING BRACKETS REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		84	
		1	30	30	6.25																								BACK-TO-BACK	X		
		1	6	10	0.42																								SIGN ID CODE RI-1 SIGN ID CODE VD-700			T-44
C 165+79.0, RT	Chester Depot	1	30	18	3.75						1					X		X											SIGN ID CODE VD-018		85	
C 165+91.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X											SIGN ID CODE VR-017			E-141
C 166+06.0, LT	STOP	1	30	30	6.25						1					X		X											SIGN ID CODE RI-1	X		
C 166+25.0, LT	First Ave	1	30	8	1.67						1					X		X											DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		84	
C 166+40.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X											SIGN ID CODE VR-017			E-141
C 168+90.0, RT	SPEED LIMIT 30	1	24	30	5.00						1					X		X											SIGN ID CODE R2-1	X		
C 171+50.0, RT		1	30	30	6.25						1					X		X											SIGN ID CODE WII-2 SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	X		
	AHEAD	1	24	12	2.00																								SIGN ID CODE WI6-9P SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	X		
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF	LF 112	LF		EA		LB	LB	LB	LB									
	TOTALS				SF 44.93	SF	EA.	SF				LF			LF 112					EA.	LB				EA.	EA.	LB							

CHESTER TRAFFIC SIGN SUMMARY SHEET #16

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(I)

FILE NAME: z13c518tss_seg01.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS
PLOT DATE: 3/27/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 74 OF 309