STATE OF VERMONT
AGENCY OF TRANSPORTATION

CHESTER TRAFFIC SIGN SUMMARY SHEET 23

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR STEEL Ø (In) FOUND-ATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
CHESTER VT. ROUTE 103: C 217+04.0, LT	Chester Depot	1	30	18	3.75						1					X		X												SIGN ID CODE VD-018		85	
C 222+80.0, LT ~~C 220+29.0, LT~~		1	30	30	6.25						1					X		X												SIGN ID CODE W11-2 SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	X		
	~~AHEAD~~	~~1~~	~~24~~	~~12~~	~~2.00~~																									SIGN ID CODE ~~W16-9P~~ W16-4 SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	X		
C 222+80.0, LT	NEXT 500 FT	1	30	24	5.00																												
C 220+86.0, LT	Dairymple St / North St / STOP 1030 1407 0418	1 1	42 30	8 8	2.33 1.67						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1. TWO TOP MOUNTING BRACKETS REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST. BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		85 85	
		1 1	30 6	30 10	6.25 0.42																										X		T-44
C 221+31.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X												SIGN ID CODE VR-017			E-141
C 224+27.0, LT	Church St / North St / STOP 1030 1407 0426	1 1	30 30	8 8	1.67 1.67						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1. TWO TOP MOUNTING BRACKETS REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST. BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		84 85	
		1 1	30 6	30 10	6.25 0.42																										X		T-44
C 224+62.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X												SIGN ID CODE VR-017			E-141
C 225+01.0, RT	STATE HIGHWAY BRIDGE	1	24	18	3.00						1					X		X												SIGN ID CODE VR-039			E-141
	SPEED LIMIT 40	1	24	30	5.00																									SIGN ID CODE ~~W2-1~~ W2-4	X		
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF 98	LF	LF	EA			LB	LB	LB	LB									
	TOTALS				SF 50.68	SF	EA.	SF				LF			LF 98					EA.	LB				EA.	EA.	LB						

CHESTER TRAFFIC SIGN SUMMARY SHEET #23

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(1)

FILE NAME: z13c518tss_seg01.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS
PLOT DATE: 3/27/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 81 OF 309