STATE OF VERMONT
AGENCY OF TRANSPORTATION

CHESTER TRAFFIC SIGN SUMMARY SHEET 25

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																			REMARKS	SIGN DETAIL		
		EA	WIDTH (In)	HEIGHT (In)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (In) lb/ft			ANCHOR	SLEEVE	TUBULAR STEEL Ø (In) lb/ft					W-SHAPE STEEL				SIGN FRAME REQUIRED		DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
																														SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
												1.12	2.0	3.0	1.75	2.0	2.5			FOUND-ATION	3.0	3.5	4.0	5.0	FTG. SIZE		WEIGHT	POST SIZE					
															1.88	2.42	3.35				7.6	9.0	10.8	14.6	24"	30"						
SIGN #5, LT	SOUTH	1	24	12	2.00						1					X		X												SIGN ID CODE M3-3, BLACK ON WHITE	X		
	35	1	24	24	4.00																									SIGN ID CODE VMI-5A, BLACK ON WHITE			E-136C
	THIS SHEET SUBTOTAL				6.00											14																
	SHEET 59 SUBTOTAL SHEET 60 SUBTOTAL SHEET 61 SUBTOTAL				52.08 41.92 45.67		- - 1									56 98 84	28 - 14															
	SHEET 62 SUBTOTAL SHEET 63 SUBTOTAL SHEET 64 SUBTOTAL				33.67 54.17 73.00											84 56 168	- 14 -															
	SHEET 65 SUBTOTAL SHEET 66 SUBTOTAL SHEET 67 SUBTOTAL				57.24 55.74 76.81											84 112 42	- - 56															
	SHEET 68 SUBTOTAL SHEET 69 SUBTOTAL SHEET 70 SUBTOTAL				41.03 38.28 72.88											28 56 98	42 14 28															
	SHEET 71 SUBTOTAL SHEET 72 SUBTOTAL SHEET 73 SUBTOTAL				71.29 63.80 61.35											84 70 56	28 28 -				- - 2	- - 202											
	SHEET 74 SUBTOTAL SHEET 75 SUBTOTAL SHEET 76 SUBTOTAL				44.93 51.24 48.93											112 70 56																
	SHEET 77 SUBTOTAL SHEET 78 SUBTOTAL SHEET 79 SUBTOTAL				41.49 59.68 58.00											84 84 112	- 28 14															
	SHEET 80 SUBTOTAL SHEET 81 SUBTOTAL SHEET 82 SUBTOTAL				45.59 50.68 70.26											42 98 56	28 - 42															
	ROUNDING				9.27											16	6					8										
												LF	LF	LF	LF	LF 1920	LF 370		EA		LB 210	LB	LB	LB								
	TOTALS				SF 1325	SF	EA. 1	SF				LF			LF 2290					EA. 2	LB 210				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

CHESTER TRAFFIC SIGN SUMMARY SHEET #25

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(1)

FILE NAME: z13c518tss_seg01.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS
PLOT DATE: 3/27/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS