STATE OF VERMONT
AGENCY OF TRANSPORTATION

SPRINGFIELD TRAFFIC SIGN SUMMARY SHEET 15

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.1	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR STEEL Ø (In) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 11	5.0 lb/ft 15	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
SPRINGFIELD VT. ROUTE 11: S 252+81.0, LT		1	30	30	6.25				1																					SIGN ID CODE W11-2 SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND PROPOSED SIGN TO BE MOUNTED TO EXISTING SIGN POST	X		
		1	24	12	2.00																									SIGN ID CODE W16-7P SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND PROPOSED SIGN TO BE MOUNTED TO EXISTING SIGN POST	X		
S 254+68.0, RT		1	30	30	6.25				1																					SIGN ID CODE W11-2 SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND PROPOSED SIGN TO BE MOUNTED TO EXISTING SIGN POST	X		
		1	24	12	2.00																									SIGN ID CODE W16-7P SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND PROPOSED SIGN TO BE MOUNTED TO EXISTING SIGN POST	X		
S 254+98.0, LT		1	30	30	6.25				1																					SIGN ID CODE W11-2 SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND PROPOSED SIGN TO BE MOUNTED TO EXISTING SIGN POST	X		
		1	24	12	2.00																									SIGN ID CODE W16-7P SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND PROPOSED SIGN TO BE MOUNTED TO EXISTING SIGN POST	X		
	0110 1418 0483	1	6	10	0.42				1																					SIGN ID CODE VD-700 PROPOSED SIGN TO BE MOUNTED TO EXISTING SIGN POST			T-44
S 257+57.0, LT		1 1	30 30	30 30	6.25 6.25						1					X		X												BACK-TO-BACK SIGN ID CODE W11-2 SIGN ID CODE W11-2 SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	X X		
		1 1	24 24	12 12	2.00 2.00																								BACK-TO-BACK SIGN ID CODE W16-7PR SIGN ID CODE W16-7P SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	X X		
S 258+66.0, LT	WEST	1	24	12	2.00						1					X		X												SIGN ID CODE M3-4, GREEN ON WHITE	X		
	VERMONT 11	1	24	24	4.00																									SIGN ID CODE MI-5, GREEN ON WHITE			E-136B
S 261+57.0, LT	SPEED LIMIT 25	1	24	30	5.00						1					X		X												SIGN ID CODE R2-1	X		
												LF	LF	LF	LF	LF 42	LF		EA		LB	LB	LB	LB								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."		TOTALS	SF 52.67	SF	EA.	SF						LF				LF 42			EA.		LB				EA.	EA.	LB							

SPRINGFIELD TRAFFIC SIGN SUMMARY SHEET #15

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(I)

FILE NAME: zI3c518tss_seg02.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS
PLOT DATE: 3/27/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 153 OF 309