STATE OF VERMONT
AGENCY OF TRANSPORTATION

SPRINGFIELD TRAFFIC SIGN SUMMARY SHEET 16

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (In)	SIGN DIMENSIONS HEIGHT (In)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.1	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (In) lb/ft 1.75 / 1.88	SQUARE STEEL (In) lb/ft 2.0 / 2.42	SQUARE STEEL (In) lb/ft 2.5 / 3.35	ANCHOR	SLEEVE	TUBULAR STEEL Ø (In) FOUND-ATION	TUBULAR STEEL Ø (In) lb/ft 3.0 / 7.6	TUBULAR STEEL Ø (In) lb/ft 3.5 / 9.0	TUBULAR STEEL Ø (In) lb/ft 4.0 / 11	TUBULAR STEEL Ø (In) lb/ft 5.0 / 15	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REQUIRED FOR SIGNING	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
SPRINGFIELD VT. ROUTE 11: S 260+55.0, LT							1				1					X		X												SALVAGED SIGN TO BE MOUNTED ON NEW POST	-	-	-
							1																							SALVAGED SIGN TO BE MOUNTED ON NEW POST	-	-	-
S 261+58.0, RT	Main St STOP	1	36	12	3.00						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO IN STALL SIGN ON POST. COST ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		163	
		1	30	30	6.25																									SIGN ID CODE R1-1	X		
S 261+72.0, RT		1 1	18 18	18 18	2.25 2.25						1					X		X												BACK-TO-BACK SIGN ID CODE OM1-1 SIGN ID CODE OM1-1	X X		
S 261+77.0, RT	SCHOOL GATE AT PORTAGE & SPRINGFIELD HIGH SCHOOL						1				1					X		X												SALVAGED SIGN TO BE MOUNTED ON NEW POST	-	-	-
S 261+80.0, RT	EAST	1	24	12	2.00						1					X		X												SIGN ID CODE M3-2, GREEN ON WHITE	X		
	VERMONT 11	1	24	24	4.00																									SIGN ID CODE M1-5, GREEN ON WHITE			E-136B
		1	21	15	2.19																									SIGN ID CODE M6-2L, GREEN ON WHITE	X		
	0110 1418 0496	1	6	10	0.42																									SIGN ID CODE VD-700			T-44
S 262+40.0, RT	Mineral St STOP 0110 1418 0497	1	42	12	3.50						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO IN STALL SIGN ON POST. COST ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		163	
		1 1	30 6	30 10	6.25 0.42																									BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700	X		T-44
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF	LF 84	LF		EA		LB	LB	LB	LB									
		TOTALS			SF 32.53	SF	EA. 3	SF				LF			LF 84					EA.	LB				EA.	EA.	LB						

SPRINGFIELD TRAFFIC SIGN SUMMARY SHEET #16

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(1)

FILE NAME: z13c518tss_seg02.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS
PLOT DATE: 3/27/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 154 OF 309