STATE OF VERMONT
AGENCY OF TRANSPORTATION

SPRINGFIELD TRAFFIC SIGN SUMMARY SHEET 19

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.1	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR STEEL Ø (In) FOUND-ATION	3.0 7.6	3.5 9.0	4.0 11	5.0 15	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMOVED	REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
SPRINGFIELD VT. ROUTE 11:																																	
S 278+16.0, RT	Loveland St / Clinton St / STOP 0110 1418 0527	1	42	12	3.50						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1		163	
		1	42	12	3.50																								DOUBLE SIDED SIGN, SIGN ID CODE D3-1. TWO TOP MOUNTING BRACKETS REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		163	
		1	30	30	6.25																								BACK-TO-BACK	X		
		1	6	10	0.42																								SIGN ID CODE RI-1 SIGN ID CODE VD-700			T-44
S 283+49.0, RT	EMERGENCY SIGNAL	1	42	30	8.75																								SIGN ID CODE RIO-13 SIGN TO BE MOUNTED ON EXISTING SIGNAL MAST.	X		
S 283+92.0, LT	STOP 0110 1418 0538	1	30	30	6.25						1					X		X												BACK-TO-BACK	X		
		1	6	10	0.42																								SIGN ID CODE RI-1 SIGN ID CODE VD-700			T-44
S 284+18.0, LT	TO	1	24	12	2.00						1					X		X												SIGN ID CODE M4-5, BLACK ON WHITE	X		
	143	1	30	24	5.00																								SIGN ID CODE VMI-5A, BLACK ON WHITE			E-136C
S 284+45.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X												SIGN ID CODE VR-017			E-141
S 284+64.0, LT	Bridge St / Clinton St	1	42	12	3.50						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1. TWO TOP MOUNTING BRACKETS REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		163	
		1	42	12	3.50																								DOUBLE SIDED SIGN, SIGN ID CODE D3-1		163	
S 284+78.0, RT	EMERGENCY SIGNAL	1	42	30	8.75																								SIGN ID CODE RIO-13 SIGN TO BE MOUNTED ON EXISTING SIGNAL MAST.	X		
												LF	LF	LF	LF	LF 70	LF		EA		LB	LB	LB	LB								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."		TOTALS	SF 56.84	SF	EA.	SF						LF			LF 70					EA.	LB				EA.	EA.	LB						

SPRINGFIELD TRAFFIC SIGN SUMMARY SHEET #19

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(1)

FILE NAME: z13c518tss_seg02.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS
PLOT DATE: 3/27/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 157 OF 309