WINDSOR QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

ROADWAY U.S. ROUTE 5	ROADWAY VT. ROUTE 44	BRIDGE	TOTALS GRAND TOTAL	TOTALS FINAL	UNIT	DESCRIPTIONS ITEMS	ITEM NUMBER	ROUND
100	400		500		LB	FERTILIZER	651.18	EST.
0.4	1.6		2		TON	AGRICULTURAL LIMESTONE	651.20	EST.
0.4	1.6		2		TON	HAY MULCH	651.25	EST.
10	40		50		CY	TOPSOIL	651.35	EST.
230			230		CY	TEMPORARY EROSION MATTING	653.20	8.0
80	795		875		SF	TRAFFIC SIGNS, TYPE A	675.20	5.20
230	1880		2110		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	10.0
52	163		215		EACH	REMOVING SIGNS	675.50	-
19			19		EACH	ERECTING SALVAGED SIGNS	675.60	-
	12		12		EACH	DELINEATOR WITH STEEL POST	676.10	-
737			737		LF	VEHICLE LOOP DETECTOR	678.22	-
1			1		EACH	SPECIAL PROVISION (PEDESTRIAN SIGNAL HEADS, COUNTDOWN) (U.S. ROUTE 5 @ STATE ST)	900.620	-
400	850		1250		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	90.0
10	15		25		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE II)	900.680	EST.
210	580		790		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	4.0

QUANTITIES	UNIT	ITEMS

WINDSOR QUANTITY SHEET #3

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(1)

FILE NAME: z13c518qty_seg04.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS
PLOT DATE: 4/1/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 229 OF 309