STATE OF VERMONT
AGENCY OF TRANSPORTATION

WINDSOR TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR STEEL Ø (In) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SHSM REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
WINDSOR U.S. ROUTE 5: W 196+12.0, RT	PARKING PARKING						1 1				1					X		X												BACK-TO-BACK SALVAGED SIGNS TO BE MOUNTED ON NEW POST.	-	-	-
W 196+54.0, RT	Depot Ave / Main St 0050 1423 0372	1	30	8	1.67				1																					DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 PROPOSED SIGNS TO BE MOUNTED TO EXISTING SIGN ASSEMBLY		302 302	
		1	24	8	1.33																									TWO TOP MOUNTING BRACKETS REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST. SIGN ID CODE VD-700			T-44
		1	6	10	0.42																												
W 201+89.0, LT	Pvt Maxwell Perkins Ln / Pvt Maxwell Perkins Ln	1	66	8	3.67						2					X		X												BACK-TO-BACK SIGN ID CODE D3-1 SIGN ID CODE D3-1		302 302	
		1	66	8	~~3.67~~ 0 TEXT ON BOTH SIDES																									TWO TOP MOUNTING BRACKETS REQUIRED TO INSTALL SIGNS ON POSTS. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.			
	RESERVED PARKING						1																							SALVAGED SIGN TO BE MOUNTED ON NEW POST	-	-	-
W 205+09.0, RT	Everett Ln / Main St / STOP 0050 1423 0388	1	30	8	1.67						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TWO TOP MOUNTING BRACKETS REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		303 302	
		1	24	8	1.33																									BACK-TO-BACK SALVAGED SIGN TO BE MOUNTED ON NEW POST SIGN ID CODE VD-700	-	-	- T-44
		1	6	10	0.42		1																										
W 207+79.0, LT	Pvt Runnemede Ln	1	42	8	2.33						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		303	
WINDSOR U.S. ROUTE 44: W 84+00.0, LT	SOUTH WEST	1	24	12	2.00						2					X		X											#2	SIGN ID CODE M3-3, GREEN ON WHITE SIGN ID CODE M3-4, GREEN ON WHITE	X X		
		1	24	12	2.00																												
	VERMONT 44A / VERMONT 44	1	24	24	4.00																									SIGN ID CODE MI-5, GREEN ON WHITE SIGN ID CODE MI-5, GREEN ON WHITE			E-136B E-136B
		1	24	24	4.00																												
		1	21	15	2.19																									SIGN ID CODE M6-2L, GREEN ON WHITE SIGN ID CODE M6-3, GREEN ON WHITE	X X		
		1	21	15	2.19																												
												LF	LF	LF	LF	LF 98	LF		EA		LB	LB	LB	LB									
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."		TOTALS			SF ~~32.89~~ 29.22	SF	EA. 4	SF				LF			LF 98					EA.	LB				EA.	EA.	LB							

WINDSOR TRAFFIC SIGN SUMMARY SHEET #4

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(1)

FILE NAME: z13c5181ss_seg04.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS
PLOT DATE: 3/27/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 284 OF 309