STATE OF VERMONT
AGENCY OF TRANSPORTATION

WINDSOR TRAFFIC SIGN SUMMARY SHEET 10

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR STEEL Ø (In) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	FOUNDATION REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
WINDSOR VT. ROUTE 44: W 170+82.0, RT	⟸	1	48	24	8.00						2					X		X												SIGN ID CODE WI-6L SIGN SHALL HAVE FLUORESCENT YELLOW BACKGROUND	X		
W 171+28.0, RT	⟹	1	48	24	8.00						2					X		X												SIGN ID CODE WI-6R SIGN SHALL HAVE FLUORESCENT YELLOW BACKGROUND	X		
W 173+50.0, RT	SPEED LIMIT 40	1	24	30	5.00						1					X		X												SIGN ID CODE R2-1	X		
W 176+75.0, LT	⚠	1	30	30	6.25						1					X		X												SIGN ID CODE WI-5L SIGN SHALL HAVE FLUORESCENT YELLOW BACKGROUND	X		
	30 M.P.H.	1	18	18	2.25																									SIGN ID CODE WI3-IP SIGN SHALL HAVE FLUORESCENT YELLOW BACKGROUND	X		
W 186+55.0, RT	⚠ SPEED LIMIT 25	1	36	36	9.00						2					X		X												SIGN ID CODE W3-5	X		
	0440 1423 0353	1	6	10	0.42																									SIGN ID CODE VD-700			T-44
W 190+84.0, RT	SPEED LIMIT 25	1	30	36	7.50						1					X		X												SIGN ID CODE R2-1	X		
W 190+84.0, LT	SPEED LIMIT 40	1	24	30	5.00						1					X		X												SIGN ID CODE R2-1	X		
W 190+98.0, LT	Pvt Harris Rd	1	36	8	2.00						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TOP MOUNTING BRACKET REQUIRED TO INSTALL SIGN ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		303	
												LF	LF	LF	LF 154	LF	LF	EA		LB	LB	LB	LB									
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."	TOTALS				SF 53.42	SF	EA.	SF				LF			LF 154					EA.	LB				EA.	EA.	LB						

WINDSOR TRAFFIC SIGN SUMMARY SHEET #10

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(I)

FILE NAME: z13c518tss_seg04.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS
PLOT DATE: 3/27/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 290 OF 309