STATE OF VERMONT
AGENCY OF TRANSPORTATION

WINDSOR TRAFFIC SIGN SUMMARY SHEET 12

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR STEEL Ø (In) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGNS REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
WINDSOR VT. ROUTE 44: W 210+48.0, RT	Bavier Ave / Ascutney St / STOP 0440 1423 0398	1 1	36 36	8 8	2.00 2.00						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1. TWO TOP MOUNTING BRACKETS REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		303 303	
		1 1	30 6	30 10	6.25 0.42																								BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700	X		T-44
W 213+47.0, LT	STOP 0440 1423 0406	1 1	30 6	30 10	6.25 0.42						1					X		X												BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700	X		T-44
W 213+50.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X												SIGN ID CODE VR-017			E-141
W 213+52.0, LT	Sherwin Ave / Ascutney St	1	36	8	2.00						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 TWO TOP MOUNTING BRACKETS REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		303	
		1	36	8	2.00																								DOUBLE SIDED SIGN, SIGN ID CODE D3-1		303	
W 214+74.0, LT	Kinsey St / Ascutney St / STOP 0440 1423 0407	1 1	30 36	8 8	1.67 2.00						1					X		X												DOUBLE SIDED SIGN, SIGN ID CODE D3-1 DOUBLE SIDED SIGN, SIGN ID CODE D3-1. TWO TOP MOUNTING BRACKETS REQUIRED TO INSTALL SIGNS ON POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.		303 303	
		1 1	30 6	30 10	6.25 0.42																								BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700	X		T-44
W 215+07.0, LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X												SIGN ID CODE VR-017			E-141
W 216+12.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X												SIGN ID CODE VR-017			E-141
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."												LF	LF	LF	LF	LF 98	LF		EA		LB	LB	LB	LB									
		TOTALS			SF 46.68	SF	EA.	SF				LF			LF 98					EA.	LB				EA.	EA.	LB						

WINDSOR TRAFFIC SIGN SUMMARY SHEET #12

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(1)

FILE NAME: z13c518tss_seg04.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS

PLOT DATE: 3/27/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 292 OF 309