STATE OF VERMONT
AGENCY OF TRANSPORTATION

WINDSOR TRAFFIC SIGN SUMMARY SHEET 21

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																	REMARKS	SIGN DETAIL		
		EA	WIDTH (In)	HEIGHT (In)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (In)					TUBULAR STEEL Ø (In)					W-SHAPE STEEL				RESIGN REQUIRED	SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	DETAIL IN SHSM	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
															1.75	2.0	2.5	ANCHOR	SLEEVE	FOUND-ATION	3.0	3.5	4.0	5.0	FTG. SIZE		WEIGHT	POST SIZE				
												1.12	2.0	3.0	lb/ft						7.6	9.0	10.8	14.6	24"	30"						
															1.88	2.42	3.35															
W 259+62.0, LT		1	30	30	6.25						1					X		X											SIGN ID CODE W11-2 SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	X		
		1	24	12	2.00																								SIGN ID CODE W16-7P SIGN SHALL HAVE FLUORESCENT YELLOW GREEN BACKGROUND	X		
W 260+28.0, LT	SPEED LIMIT 25	1	24	30	5.00						1					X		X											SIGN ID CODE R2-1	X		
	THIS SHEET SUBTOTAL				13.25											28																
	SHEET 281 SUBTOTAL SHEET 282 SUBTOTAL				24.67 11.50		6 5									70 56																
	SHEET 283 SUBTOTAL SHEET 284 SUBTOTAL				27.24 32.89		3 4									98 98																
	SHEET 285 SUBTOTAL SHEET 286 SUBTOTAL				37.28 57.59											70 112																
	SHEET 287 SUBTOTAL SHEET 288 SUBTOTAL				34.85 54.92											98 182																
	SHEET 289 SUBTOTAL SHEET 290 SUBTOTAL				45.42 53.42											140 154																
	SHEET 291 SUBTOTAL SHEET 292 SUBTOTAL				49.00 46.68											112 98																
	SHEET 293 SUBTOTAL SHEET 294 SUBTOTAL				51.76 47.34											70 98	14 -															
	SHEET 295 SUBTOTAL SHEET 296 SUBTOTAL				54.60 48.43											98 98																
	SHEET 297 SUBTOTAL SHEET 298 SUBTOTAL				47.83 51.62											98 84																
	SHEET 299 SUBTOTAL SHEET 300 SUBTOTAL				41.00 38.51		- 1									98 126																
	ROUNDING				5.20											4	6															
												LF	LF	LF	LF	LF 2090	LF 20		EA		LB	LB	LB	LB								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."	**TOTALS**				SF 875	SF	EA. 19	SF				LF			LF 2110					EA.	LB				EA.	EA.	LB					

WINDSOR TRAFFIC SIGN SUMMARY SHEET #21

PROJECT NAME: CHESTER-SPRINGFIELD-ROCKINGHAM-WINDSOR
PROJECT NUMBER: STP 2952(1)

FILE NAME: z13c518tss_seg04.dgn
PROJECT LEADER: D. GOZALKOWSKI
DESIGNED BY: A. HAWKINS
PLOT DATE: 3/27/2015
DRAWN BY: A. KIRBY
CHECKED BY: J. SHIELDS
SHEET 301 OF 309