DIRECTION	MILEPOINT	LOCATION CODE (SHEET 3)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION PROJECT SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB RANDOLPH VT 12							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN									ANCHORS										"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
		F	M3-3	24	12		SOUTH / VERMONT 12 (CONT.)	2.00								4′ 1		11′-3" X								SOUTH, **GREEN ON WHITE**			E-136B
		F	VM1-5	24	24			4.00																		VT ROUTE 12			E-136B
SB	3.260	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
		F	S3-1	36	36	FYG		9.00								8′ 2		11′-4" 11′-3" X									X		
SB	3.229	F	VW-054R	30	30		HIDDEN DRIVE RIGHT						1		X														
		F	VW-054R	30	30			6.25								4′ 1		10′-1" X											E-154
SB	3.191	F	W3-5	36	36		SPEED LIMIT 25	9.00								8′ 2		9′-7" 10′-2" X								INSTALL 200 FT ± SOUTH OF EXISTING SIGN AT MP 3.229	X		
SB	3.080	F	VD-701	6	8		BRIDGE 44 VT 12						1		X												REMOVE INACURATE SIGN			
		F	VD-701	6	10		BRIDGE 43 VT-12	0.42								4′ 1		4′-10" X											T-42
SB	3.055	F	VR-038	24	18		STATE HIGHWAY ENDS			1				X															
		F	R2-1	30	36		SPEED LIMIT 25			1																			

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN)	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00	TUBULAR STEEL Ø (IN) 3.50	TUBULAR STEEL Ø (IN) 4.00	TUBULAR STEEL Ø (IN) 5.00
SHEET TOTALS	30.67	0.00	2	0	0	3	0	0	7	96′-6" ~~100.0~~	0	0.0	0.0	0.0	0.0
	SF	SF	EA	EA	EA	EA	EA	EA	EA	FT	EA	LB	LB	LB	LB
TOWN DIRECTIONAL TOTALS	153.58 ~~147.3~~	0.0	2	0	0	34	0	0	26	352.08 ~~345.0~~	2	179.23 ~~193.8~~			

PROJECT NAME: **RANDOLPH-BERLIN**
PROJECT NUMBER: **STPG SIGN(52)**
FILE NAME: **z13c626tssrandolph SB**
PROJECT MANAGER: **C. BEAN**
DESIGNED BY: **S. GOODWIN**
RANDOLPH VT-12 SOUTHBOUND 5
PLOT DATE: **5/12/2015**
DRAWN BY: **S. GOODWIN**
CHECKED **D. MUNRO**
SHEET **22** OF **105**